

**BOARD OF WATER AND SEWER COMMISSIONERS  
OF THE  
CITY OF MOBILE, ALABAMA**

**STANDARD SPECIFICATIONS  
FOR  
WATER MAINS, SANITARY SEWERS  
AND  
SEWAGE PUMPING STATIONS**

**APRIL 1993**

**UPDATED JULY 2006**

**TABLE OF CONTENTS**

**BOARD OF WATER AND SEWER COMMISSIONERS  
OF THE  
CITY OF MOBILE, ALABAMA**

**STANDARD SPECIFICATIONS  
FOR  
WATER MAINS, SANITARY SEWERS  
AND  
SEWAGE PUMPING STATIONS**

**I. GENERAL INFORMATION AND REQUIREMENTS, INVITATION,  
PROPOSAL AND CONTRACT DOCUMENTS**

GENERAL INFORMATION AND REQUIREMENTS  
INVITATION FOR BIDS  
PROPOSAL  
CONTRACT  
CONTRACT BOND  
LABOR AND MATERIAL BOND

**II. GENERAL CONDITIONS**

Paragraph

SECTION 1

DEFINITION OF TERMS

Definitions .....	1.01
AASHTO .....	1.02
ANSI .....	1.03
Addendum.....	1.04
ADEM.....	1.05
Advertisement for Bids.....	1.06
Agreement.....	1.07
ASTM .....	1.08
AWWA .....	1.09
Bid.....	1.10
Bidder.....	1.11

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Board.....	1.12
Contract.....	1.13
Contract Bid Price.....	1.14
Contract Bonds .....	1.15
Contractor .....	1.16
County.....	1.17
Developer.....	1.18
Developer's Engineer .....	1.19
DIPRA.....	1.20
Engineer .....	1.21
Equipment.....	1.22
Extra Work.....	1.23
Extra Work Orders.....	1.24
Laboratory.....	1.25
Material.....	1.26
NEMA.....	1.27
Notice to Proceed.....	1.28
OSHA.....	1.29
Owner.....	1.30
Plans (Drawings).....	1.31
Product .....	1.32
Project .....	1.33
Proposal .....	1.34
Proposal Form.....	1.35
Proposal Guaranty.....	1.36
Record Drawings .....	1.37
Resident Project Representative .....	1.38
SAHD.....	1.39
Shop Drawings.....	1.40
Specifications.....	1.41
State .....	1.42
Subcontractor .....	1.43
Superintendent .....	1.44
Supplemental Agreement.....	1.45
Surety .....	1.46
Work .....	1.47

TABLE OF CONTENTS  
(Continued)

Paragraph

SECTION 2

PROPOSAL REQUIREMENTS AND CONDITIONS

Qualifications of Bidders .....	2.01
Contents of Proposal Forms.....	2.02
Interpretation of Approximate Estimates.....	2.03
Examination of Plans and Specifications,.....	2.04
Special Provisions and Site of Work	
Preparation of Proposal.....	2.05
Irregular Proposals .....	2.06
Proposal Guaranty.....	2.07
Delivery of Proposals.....	2.08
Withdrawal or Revision of Proposal.....	2.09
Opening of Proposals.....	2.10
Disqualification of Bidders .....	2.11
Liquidated Damages .....	2.12

SECTION 3

AWARD AND EXECUTION OF CONTRACT

Consideration of Bids .....	3.01
Award of Contract.....	3.02
Return of Proposal Guarantee.....	3.03
Execution of Contract .....	3.04
Failure to Execute Contract .....	3.05
Requirements of Contract Bonds .....	3.06
Insurance .....	3.07
Indemnity Provisions .....	3.08

SECTION 4

SCOPE OF WORK

Intent of Plans and Specifications.....	4.01
Underground and Existing Utilities .....	4.02
Alteration of Plans or Character of Work.....	4.03

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Extra Work.....	4.04
Construction and Maintenance of Detours .....	4.05
Removal and Disposal of Structures and Obstructions .....	4.06
Final Clean-Up.....	4.07
Maintenance of the Work During Construction .....	4.08
Failure to Maintain Work .....	4.09

SECTION 5

CONTROL OF WORK

Authority of the Engineer .....	5.01
Plans and Shop Drawings .....	5.02
Manufacturer's Drawings .....	5.03
Conformity with Plans and Allowable Deviations .....	5.04
Coordination of Plans, Specifications, and Special Provisions .....	5.05
Cooperation of the Contractor .....	5.06
Construction Surveys.....	5.07
Resident Project Representatives.....	5.08
Inspection.....	5.09
Removal of Defective and Unauthorized Work.....	5.10
Disputed Claims.....	5.11
Contractor Initiated Changes .....	5.12
Project Completion .....	5.13
Final Construction Inspection.....	5.14
Final Acceptance.....	5.15
Maintenance Guarantee After Acceptance .....	5.16
Contract Closeout Documents .....	5.17

SECTION 6

CONTROL OF MATERIAL

Source of Supply and Quality of Materials .....	6.01
Samples and Tests.....	6.02
Storage of Materials.....	6.03
Defective Materials.....	6.04
Contractor's Title to Materials .....	6.05

SECTION 7

LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC

Laws to be Observed.....	7.01
--------------------------	------

TABLE OF CONTENTS

(Continued)

	<u>Paragraph</u>
Permits, Taxes, Licenses, Laws and Ordinances .....	7.02
Patented Devices, Materials and Processes .....	7.03
Sanitary Provisions .....	7.04
Public Convenience and Safety .....	7.05
Crossing Railroads .....	7.06
Ingress and Egress .....	7.07
Barricades, Danger, Warning and Detour Signs .....	7.08
Preservation and Restoration of Property, .....	7.09
Trees, Monuments, Et Cetera	
Responsibility for Damage Claims, Etc. ....	7.10
Right-of-Way .....	7.11
Interference of Contractors .....	7.12
Contractor's Responsibility for Work .....	7.13
Contractor's Responsibility for Completion .....	7.14
Personal Liability of Public Officials .....	7.15
No Waiver of Legal Rights .....	7.16
Use of Chemicals .....	7.17
Dust Control.....	7.18
Safety and Health Regulations for Construction .....	7.19
Bracing.....	7.20
Wetlands .....	7.21

## SECTION 8

### PROSECUTION AND PROGRESS

Subletting or Assigning of Contract .....	8.01
Notice to Proceed.....	8.02
Notice and Service Thereof .....	8.03
Prosecution of Work .....	8.04
Construction Schedule and Periodic Estimates .....	8.05
Limitations of Operations .....	8.06
Character of Workmen and Equipment .....	8.07
Temporary Suspension of Work .....	8.08
Determination and Extension of Contract Time .....	8.09
for Completion of Work	
Failure or Delay in Completing Work on Time.....	8.10
Default of Contract .....	8.11
Termination for Failure of Performance .....	8.12
Payments to Contractor.....	8.13

### TABLE OF CONTENTS

(Continued)

	<u>Paragraph</u>
Payment for Material Stored.....	8.14
Payment By Contractor.....	8.15
Furnishing of Utilities.....	8.16
Monthly Estimates.....	8.17
Extra and Force Account Work.....	8.18
Acceptance of Final Payment Constitutes Release.....	8.19
Disturbed Areas.....	8.20

## SECTION 9

### TESTING MATERIALS

Inspection and Testing of Materials.....	9.01
Portland Cement.....	9.02
Aggregates for Use in Cement Concrete.....	9.03
Fine Aggregate.....	9.04
Coarse Aggregate.....	9.05
Slump Tests of Concrete.....	9.06
Advance Concrete Tests.....	9.07
Concrete Design Mix and Tests.....	9.08
Concrete Control Tests (Laboratory Curing).....	9.09
Reinforcing Steel.....	9.10
Structural Steel.....	9.11
Steel Bar Joists.....	9.12
Brick.....	9.13
Building Block and Stone.....	9.14
Concrete Sewer Pipe.....	9.15
Cast Iron, Ductile Iron Pipe and Special Castings.....	9.16
Other Materials and Equipment.....	9.17

### III. CONSTRUCTION SPECIFICATIONS

## SECTION 10

### SPECIAL PROVISIONS

Alabama Act No. 84-228.....	10.01
Small and Small Underutilized Businesses.....	10.02
State Highway or Railroad Permits.....	10.03
Permits, Certificates, Laws and Ordinances.....	10.04
Wage Rates.....	10.05

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Sequence of Operations .....	10.06
Project Documentation .....	10.07
Reports, Records and Data.....	10.08
Signs.....	10.09
Construction Within State Highway Right-of-Way.....	10.10
Cutting of Trees Within Public Rights-of-Way .....	10.11
Dewatering.....	10.12
Weather Conditions .....	10.13
Locks and Keys.....	10.14
Tightness of Water Containing Walls.....	10.15
Extension of Contract Time .....	10.16
Clean-Up.....	10.17
Brands of Equipment and Materials .....	10.18
Affidavit of Compliance .....	10.19
Supervision of Installation and the Guarantee .....	10.20
Manufacturer's Certification .....	10.21
Maximum Trench Width.....	10.22
Basis of Payment and Method of Measure .....	10.23
Special Handling of Purchase Orders .....	10.24
Bypass Pumping.....	10.25

SECTION 11

WATER MAINS

Scope.....	11.01
Work Included .....	11.02
Materials .....	11.03
Inspection.....	11.04
Handling Pipe and Accessories.....	11.05
Removing and Replacing Pavement .....	11.06
Alignment and Grade.....	11.07
Excavation and Preparation of Trench.....	11.08
Pipe Laying .....	11.09
Jointing Pipe .....	11.10

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Setting Valves, Valve Boxes, Fittings ..... and Blow-Offs	11.11
Setting Hydrants .....	11.12
Plugging Dead Ends.....	11.13
Anchorage of Bends, Tees and Plugs .....	11.14
Chlorination of Completed Pipeline .....	11.15
Hydrostatic Testing.....	11.16
Concrete .....	11.17
Backfilling .....	11.18
Erosion Control.....	11.19
Maintenance of Surfaces.....	11.20
Clean-Up.....	11.21
Pressure Tests and Chlorination Adjacent..... to Existing Water Lines	11.22
Existing Water System.....	11.23
Dust Control.....	11.24
Public Safety .....	11.25
Extra Depth for Water Lines.....	11.26
Tapping of Water Mains .....	11.27
Encasement Pipe .....	11.28
Backflow Prevention.....	11.29

SECTION 12

SANITARY SEWERS

Scope.....	12.01
Work Included .....	12.02
Materials .....	12.03
Precast Manhole.....	12.04
Brick Manhole .....	12.041
Ceramic Epoxy Lining for Precast Manholes.....	12.05
Castings.....	12.06
Manhole Steps.....	12.07
Drop Connections for Manholes.....	12.08
Concrete .....	12.09
Brick.....	12.10

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Mortar for Sewer Structures .....	12.11
Running Boards, Saddle Piles and Mats .....	12.12
Crushed Slag or Crushed Stone Foundation .....	12.13
Embedment of PVC Pipe for Gravity Sewers.....	12.14
Embedment of Polyethylene Sewer Pipe .....	12.15
Backfilling .....	12.16
Erosion Control.....	12.17
Grade.....	12.18
Establishing Grade .....	12.19
Excavation .....	12.20
Removing and Replacing Pavement .....	12.21
Pumping and By-Passing .....	12.22
Coupling of Dissimilar Pipes .....	12.23
Laying Sewer Pipe .....	12.24
Bracing.....	12.25
Creek Crossings .....	12.26
Installation of Force Mains .....	12.27
Air and Vacuum Valves for Force Mains .....	12.28
Infiltration .....	12.29
Air Testing of Sewers .....	12.30
Clean-Up.....	12.31
Internal Video Inspection.....	12.32
Cleaning of Sewer Main .....	12.33

SECTION 13

SEWAGE PUMPING STATION

(Submerged Pump Type)

Scope.....	13.01
Materials .....	13.02
Intent of Plans and Specifications.....	13.03
Submittals and Tests .....	13.04
Clearing.....	13.05
Excavation for Pipes and Structures .....	13.06
Concrete .....	13.07

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Wet-Well.....	13.08
Ceramic Epoxy Lining for Wet-Well .....	13.09
Backfill for Pipes and Structures .....	13.10
Topsoil .....	13.11
Solid Sod.....	13.12
Fence.....	13.13
Access Drive .....	13.14
Submersible Pumps.....	13.15
Valves and Piping .....	13.16
Electrical .....	13.17
Continuity of Operations .....	13.18
Electric Power Metering .....	13.19
Electrical Service .....	13.20
Definition of Acceptance .....	13.21
Clean-Up.....	13.22
Controls and Communication .....	13.23
Lift Station Control Specifications .....	13.24
Specifications for Remote Telemetry .....	13.25
Specifications for Radios .....	13.26

SECTION 14

REMOVING AND REPLACING PAVEMENT

Scope.....	14.01
Materials .....	14.02
Removing and Replacing Pavement .....	14.03

SECTION 15

BACKFILLING

Scope.....	15.01
Materials .....	15.02
Backfilling .....	15.03
Backfilling for Sewage Pumping Stations .....	15.04

TABLE OF CONTENTS  
(Continued)

Paragraph

SECTION 16

EROSION CONTROL

Scope.....	16.01
Erosion Control and Property Protection.....	16.02
Materials and Construction Requirements.....	16.03
Method of Measurement and Basis of Payment .....	16.04

SECTION 17

ENCASEMENT PIPE

Scope.....	17.01
General.....	17.02
Material.....	17.03
Filling Encasement .....	17.04
Encasement Spacers.....	17.05

SECTION 18

REHABILITATION OF SANITARY SEWER MAINS BY THE  
CURED-IN-PLACE (CIPP) METHOD

Scope.....	18.01
Materials .....	18.02
Construction Procedures .....	18.03
Construction Methods.....	18.04
Post Televising of Completed Sections .....	18.05
CIPP Contractor Qualifications .....	18.06
Warranty .....	18.07

SECTION 19

REHABILITATION OF MANHOLES

Scope.....	19.01
Lining of Manholes.....	19.02
Replacement of Manhole Frame and Cover .....	19.03
Salvaging Manhole Frame and Cover .....	19.04
Raising of Existing Manhole Frame and Cover.....	19.05
Inflow Dish .....	19.06

TABLE OF CONTENTS  
(Continued)

	<u>Paragraph</u>
Chimney Seal .....	19.07
Manholes Lacking Benches and Inverts .....	19.08
Manhole Rehabilitation Contractor Qualifications.....	19.09
Vacuum Testing.....	19.10
Manhole Rehabilitation Warranty .....	19.11

SECTION 20

HORIZONTAL DIRECTIONAL DRILLING (HDD)/HDPE PIPE

Scope.....	20.01
Materials .....	20.02
Installation .....	20.03
Drilling Operations .....	20.04

SECTION 21

REHABILITATION OF SANITARY SEWER MAINS BY THE PIPE  
BURSTING AND TRENCHLESS PIPE REPLACEMENT METHOD

Scope.....	21.01
Materials .....	21.02
Construction Procedures.....	21.03
Construction Methods.....	21.04
Testing .....	21.05
Post Televising of Completed Sections .....	21.06

APPENDICES

APPENDIX A	List of Acceptable Products and Approved Manufacturers
APPENDIX B	Water Line Construction Details (1 Sheet)
APPENDIX C	Sanitary Sewer Construction Details (2 Sheets)
APPENDIX D	Sewage Pumping Station Details (1 Sheet)
APPENDIX E	Sewage Pumping Station Electrical Details (1 Sheet)
APPENDIX F	Project Sign Detail (1 Sheet)

APPENDIX G	Policy for the Control of Backflow and Cross-Connections
APPENDIX H	Small and Small Disadvantaged Business
APPENDIX I	Trench Widths and Paving Cut-Backs
APPENDIX J	Irrevocable Standby Letter of Credit
APPENDIX K	Installation Details by Lift Station Loop Number Assignments for Duplex Pump Stations Loop Number Assignments for Single Pump Stations Sewage Pumping Station Wiring & Control Logic Sewage Pumping Station Electrical Details for New Installation RTU Details for Existing Control Panel Electrical Details for Building Revisions
APPENDIX L	Sewer Cleanout Detail & Service Connection To Lined S.S. Mains