



ADDENDUM NO. 3
TO THE CONTRACT DOCUMENTS Project No.: D3755100

Date: March 24, 2026

for the construction of
WRIGHT SMITH JR WWTP ELECTRICAL, I & C AND HVAC MODIFICATIONS PROJECT
MOBILE AREA WATER AND SEWER SERVICES (MAWSS)
MOBILE, AL

To All Planholders and/or Prospective Bidders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of Wright Smith Jr WWTP Electrical, I & C and HVAC Modifications Project dated January 2026 as fully and completely as if the same were fully set forth therein:

A. **PART 1—MAWSS STANDARD SPECIFICATIONS**

1. The Proposal form is hereby reissued in its entirety for use by all bidders with significant changes as follows:
 - revise alternate bid 3 to replace the high-mast light fixture bulbs rather than the entire fixture
 - revise alternate bid 5 to obtain a unit price for replacement of high-mast light fixture bulbs rather than the entire fixture
 - change Alternate 6 into Alternates 6 and 7 with single bid amounts for the buildings as indicated under each alternate
 - Renumber Alternates 7 and 8 to be Alternates 8 and 9 and request a single bid amount total for the various wire sizes.
2. Section 01 11 00 Summary of Work is hereby reissued in its entirety with changes to reflect the changes in the Proposal form and also indicate the inclusion of the primary power service and transformer within the project scope of work.

B. **PART 2—TECHNICAL SPECIFICATIONS**

1. Specification Section 40 90 00 is revised to delete subparagraphs 1.01.B.3.g.1 thru 3 and add subparagraphs 1.01.B.21 to read as follows:
 21. Incorporate the existing SCADA Network Panel in the Sludge Pump and Gas Generation Building (Facility 56) into the new fiber optic loop for the control network. The existing network connection is single-mode fiber. Convert the components in this panel to be compatible with the new fiber optic network.
 - a. Install networking equipment, fiber optic components, and other panel components as identified in the Drawings and Specifications. b. PICS is responsible for supplying components necessary to deliver a fully functional network control panel.

- b. Remove existing network and fiber optic components that are deemed unnecessary once the new fiber optic control network is installed.
 - c. Coordinate with Owner regarding whether removed components should be returned to the Owner or discarded appropriately.
 - d. Configuration of Ethernet switch shall be by ASP.
2. Specification Section 40 90 00 Supplements 2, 3, and 4 are reissued to include changes as indicated.
 3. Revise 40_90_00 Supplement 3 as reissued to ADD I/O for the bypass contact state of Secondary Effluent Pumps 1 and 2.

C. **PART 3—DRAWINGS**

1. Revise Drawing 05-E-2001(as issued with Addendum 2) to Delete P01, P02 and the new transformer at 58-OEB and reroute P10 to run from the manhole to the existing transformer (to be replaced) (See item 3 and 6 below for sequencing notes)
2. Revise all 58-Operations Electric Building (58- OEB) Drawings to delete the transformer. Retain the driveway as per Drawing 05-C-2002.
3. Revise Power Ductbank Sections of Drawing 05-E-6003 (as issued with Addendum 2) as follows:
 - Delete sections P01 and P02.
 - Delete the [1000E3] connection from the existing boiler main disconnect to the main switchboard in sections P05, P06, and P09.
 - Add to sections P05, P06, and P09 the [2500E3] feed from main switchboard to existing/new transformer.
 - Show the [2500E3] conduits routed parallel to the other contents of these ductbank sections rather than incorporated into the same duct.
 - Route the [2000E4] conduits for the generator connection to the main switchboard with the [2500E3] conduits.
 - Delete the [1000E3] feed to the 800A disconnect feeding the boiler as indicated in section P10 and replace it with [2500E3] (6 conduits for: (6) 3-1/2”C, 3#600,#350G) to be constructed in two phases. Install three of the parallel runs of [2500E3] as Phase 1, intercepting the existing three 3-1/2” conduits running from the transformer to the removed 800A boiler feed breaker. This will provide a connection from the transformer to the main switchboard in 58-OEB. Install the additional three parallel runs of [2500E3] as Phase 2, run from the manhole to the transformer. This will complete the full set of 6

conductors per phase for the [2500E3] circuit from the transformer to 58-OEB. (See item 6 below for sequencing notes)

4. Revise Drawing 06-E-6001 as follows:
 - Change “Alabama Power Company Transformer” to “Primary Service Transformer”
 - Add transformer rating information (2000kVA, 22.86kV Delta – 480Y/277V, 5.75% impedance.
 - Change the incoming power feed from [3200E3] to be [2500E3]
 - Change the main switchboard’s main breaker trip rating to 2500A.
 - Add General Note 5 as follows: “Switchboard feed shall be initially from the existing transformer. Contractor shall replace the transformer once all power demands from the existing 52 - Generator Electrical Building have been disconnected.”
 - Delete the [1000E3] feed to the 800A existing boiler disconnect.
 - Delete the 800A feed breaker in the main switchboard for the existing boiler.
5. Revise all 52-E Drawings to mark the existing transformer for replacement, mark the exterior 800A breaker cabinet for demolition, and add a note as follows: “Contractor shall replace the transformer once all power demands from the existing 52 - Generator Electrical Building have been disconnected.”
6. Revise Drawing 01-G-005 Sequence of Construction to include the following notes:
 - 10. Interruption of utility power for removal of the boiler feed leads at the existing incoming power transformer shall be coordinated with MAWSS to allow generator support of the plant operations through the existing switchboard in 52 - Generator Electrical Building. Outage shall be no more than 4 hours and shall occur during daylight hours.
 - 11. Installation of duct bank P10 shall occur in two phases. Phase 1 shall intercept the existing duct bank of 3 3-1/2” conduits routed from the transformer to the 800A boiler feed disconnect. Interruption of utility power for Phase 1 connection of 58-OEB to the existing primary power transformer shall be coordinated with MAWSS to allow generator support of the plant operations through the existing switchboard in 52 - Generator Electrical Building. Outage shall be no more than 4 hours and shall occur during daylight hours.
 - 12. While the plant main power feed is in the Phase 1 configuration:
 - o Its ampacity shall be ~1260A.

- Coordinate switchboard selection to initially set the main breaker trip setting or rating plug at 1250A.
 - Confirm switchboard power metering is functional and will provide accurate power information to the Owner.
 - Coordinate with Owner: movement of plant loads from 52-GEB to 58-OEB and equipment run from 58-OEB in order to limit the demand through the reduced plant main power feed while in this configuration.
- 13. Phase 2 of the installation of duct bank P10 shall occur after all loads have been moved to 58-OEB. Phase 2 shall include:
 - The temporary removal of the existing transformer and removal of the power feeds from the transformer to 52-GEB
 - The installation of the 2nd half of the [2500E3] circuit in duct P10, using new conduit.
 - Updating of the main switchboard's trip setting or main rating plug to the full 2500A capacity.
 - The reinstallation of the existing transformer.
 - 14. Interruption of utility power for the Phase 2 connection shall be coordinated with MAWSS to allow generator support of the plant operations through the new switchboard in 58-OEB. Outage shall be no more than 72 hours.
 - 15. Interruption of utility power for replacement of the primary power transformer shall be coordinated with MAWSS to allow generator support of the plant operations through the new switchboard in 58-OEB. Outage shall be no more than 8 hours and shall occur during daylight hours.
7. Revise Drawing 01-G-0010 to delete General Note 3 regarding dampers on fire-rated wall penetrations.
8. Revise Drawings 05-E-2001 and 05-E-6004 as follows:
- Route an additional set of 350kcmil cable to MCC 7 in the Secondary Electrical Building from the Generator Electrical Building. The route shall utilize an existing spare 3" conduit from the Generator Electrical Building westward to the manhole at the east end of duct P13, and continue to the manhole at the west end of duct P14. Add a new 3" conduit continuing to the Secondary Electrical Building routed along the existing power duct bank P15 and p16 and extending along the existing duct bank (not shown) to the Secondary Electrical Building
 - Route an additional set of 350kcmil cable to MCC 4 in the Sludge Pump / Gas Generation from the Generator Electrical Building. The route shall utilize an existing spare 3" conduit from the Generator Electrical Building to

the Sludge Pump / Gas Generation. If the aforementioned spare is unavailable, connect to and utilize one of the existing 3" conduits routed from the to-be demolished boiler 600A breaker panel to the Sludge Pump / Gas Generation Building.

9. Revise Drawing 05-E-2001 to ADD General Note 3 to read "Bid Alternate 5 for the unit price replacement of high mast light bulbs shall replace existing bulbs with Sylvania LED120HIDR/840 or equal.
10. Revise Drawing 05-E-2002 as follows:
 - Add 6-#14 with 1 #14G discrete signal conductors between 55-PAC-1 in the Secondary Electric Building and the freestanding diesel-driven pump at the transfer pump station. Conductors shall utilize existing control conduits to reach the transfer pump station from the Secondary Electric Building. Add the I/O as indicated in the revised I/O list of 40 90 00 Supplement 3. PICS shall coordinate onsite diesel pump signals and add interposing relays in 55-CP-1 if necessary.
 - Revise Key Note 3 to require the replacement of the high mast light bulbs in addition to the lifting mechanism. Bulbs shall be Sylvania LED120HIDR/840 or equal.
11. Revise 06-E-6003 to show [150PV3] for secondary effluent pumps 1/3/4 and [175PV3] for secondary effluent pump 2. Update one-line diagram on 06-E-6004 to show integral full voltage bypasses on all four secondary effluent pump VFD's. Update secondary effluent pump control diagram on 06-E-6202 to include schematic and control signals for an integral full voltage bypass starter. Bypass starters for these drives will be integral to the units and not require an additional set of power conductors from MCC6/7
12. Drawings 06-E-0001, 06-E-0003 and 56-E shall be revised to reflect Primary Digester Mixer #2's motor is currently powered off the bus of MCC 3 with a fused disconnect located on Facility 56's north wall. Drawings 06-E-6001, 06-E-6003 and 56-E drawings shall be revised to retain the wall-mounted disconnect with the replacement feed to the disconnect off of a 30A breaker in MCC 3. Additionally, under a separate contract, a power feed to Primary Digester Mixer #1's motor is to be installed by others to be powered off the bus of MCC 3 with a fused disconnect located on Facility 56's north wall. This wall-mounted disconnect shall also be retained with the replacement feed to the disconnect off of a 30A breaker in MCC 3 of Facility 56.
13. Revise drawing 52-E-2001 to reflect circuit 2000E4 to the existing generator is to be routed though duct P11 exiting the Generator Electrical building at the southeast corner.
14. Reference Drawings 59-TY-2001, and 59-TY-6001, the drawings shall be revised to reflect that doors 101C and 102A will have electrified strikes instead of magnetic locks. Additionally, those electrified strikes will be provided and installed by others prior to this project with final connection and activation to be under this project. Door control shall be per detail 2813-005.
15. Revise Drawing 06-E-6001 to show Panel P's main breaker and bus rating as 150A.

16. Revise Drawing 06-E-6001 to indicate a 225A breaker and feed ([225E3]) to panel MB1 at the maintenance building.
17. Revise 06-E-6002 on 05-E-6003 to show [200PV3] for influent pump VFD feeds in accordance with riser on 06-E-6201. Full voltage bypass for this drive shall be integral to the unit and not require an additional set of power conductors from MCC1/2.

D. **PART 4 – March 16, 2026 PRE-BID CONFERENCE**

1. The annotated Agenda from the Pre-Bid Conference as conducted on March 16, 2026 is herewith attached for information. This agenda does not alter the contract documents but only consolidates information already found in the contract documents or included in this addendum.
2. The sign-in sheet from the Pre-Bid Conference is herewith attached for information.

E. **PART 5 - QUESTIONS AND RESPONSES (Q and R):**

1. Q: Is the security system replacement including all cameras, door locks, door status components, interconnecting fiber and recording system to be entirely provided and installed under this contract?
R: Yes. The contract documents reflect a complete and fully functional system to be provided under this contract. The only exception is the provision of limited components as indicated in the drawing changes of 59-TY drawings as indicated by this addendum.
2. Q: Who owns the incoming fiber and what coordination is required with them?
R: The incoming fiber is owned by Unity Fiber (Gabe Watson 251-391-8759). The required conduits of this project include a path for the incoming fiber to be rerouted to the Operations Electrical building. Contractor shall coordinate with Unity Fiber for the routing and terminations of that fiber so as to minimize outage of service to the WWTP.
3. Q: Where does power come from for the free-standing camera poles?
R: A: Per 05-TY-6002 and 6003, the power source for camera poles is indicated by the panel and circuit on the riser diagrams for each pole mounted SWP. For poles CP01,04 and 06, reconnect the power supply serving the existing poles.
4. Q: Where the duct bank sections indicated existing conduit, are we to assume the conduit is empty at this time?
R: No, The conduits reflected as existing but noted to be used for the fiber loops are a combination of currently empty spares or conduits currently containing existing fiber or control wiring as scheduled to be removed during the work.

5. Q: Are Owner's manuals available on the existing generator and ATS??
R: The subject drawings have not been located to date.
6. Q: New building 58 north corner is over laying an existing 4 ea-3" PVC electrical conduit run. Will the conduits need to be relocated? 4-3" PVC conduits indicate that it is a feeder or feeders to larger loads. What do they feed? What will need to be shut down to relocate conduits? Can the building foot print be shifted south to avoid the existing conduits?
R: Per Drawing 05-C-2002, the duct bank was located by Ground Penetrating Radar to have a top elevation varying from 21.4 to 24.6. adjacent to the building. The subgrade of the building's northwest corner footer is at 25.5. The subgrade of the stair landing is 23.5. As there is not a physical conflict, the ducts will not need to be relocated.
7. Q: A cost to relocate "unknown utility -see note 3 " on drawings can not be given until utility is identified. Will cost of relocating "unknown utilities" that are obstructing new construction be handled on a T&M basis during construction?
R: Per Keynote 3 of 05-C-2002, Contractor is to identify unknown utilities' contents and connection points and provide that information to MAWSS for direction. If necessary to be relocated, such relocation will be compensated using the Owner's contingency allowance.
8. Q: Ref Video Security System - Are poles purchased and installed by Security (Div 28)? If so, where are the specifications for the pole part number?
R: See Detail 2813-040 for the required pole model. The referenced work is to be completed as a part of the subject contract. Division of work by the Contractor among subcontractors is at the Contractor's discretion.
9. Q: In Addendum 1, Part 3-Drawings #3- Remove existing camera pole, cameras, and wireless equipment, who is responsible for this?
R: The referenced work is to be completed as a part of the subject contract. Division of work by the Contractor among subcontractors is at the Contractor's discretion.
10. Q: In Addendum 1, Part 3-Drawings #4 - is any demolition required besides installing new equipment?
R: Required demolition is as noted under Key Note 7. Protect the existing intercom, gate, fence and other components not indicated to be removed and coordinate reconnection as indicated.
11. Q: Drawing 99-TY-5003, detail 2813-032 and 2813-030, existing wall that could be block walls and ceilings that are not dropped tiles, are 4" boxes surface mounted?
R: Yes. Where wall-mount or ceiling-mount cameras are to be installed on existing CMU walls or exposed concrete ceilings, the termination box shall be surface-mount.
12. Q: Is a workstation/computer to be included in this bid?
R: See drawing 54-E-2001.
13. Q: Does this job has a Architectural Precast finish/ If so, are there pics or samples to match of the existing building?
R: See specification section 13 34 23 Paragraph 2.03.L. Color selection will be made during the submittal process.

14. Q: Are there any wall section drawings that shows the depth of the panels? Are the panels insulated?
R: See specification section 13 34 23 regarding wall panel minimum thickness and insulation.
15. Q: Are the panels structural or would they be cladding?
R: See specification section 13 34 23. All panels are structural.
16. Q: Drawing 01-G-0015 General Note #15 states to add a surge suppressor for circuits 600V or less. Clarify which existing panels or equipment will require new surge protectors and specify size for existing equipment.
R: This applies only to new circuits.
17. Q: Drawing 01-G-0015 General Note #32 states all underground in ductbank or outdoor cable to be tray cable. The "general circuit conductor identification in drawing 01-G-0014 shows single conductors. Clarify if underground 600V wire is to be multiconductor tray cable or single conductor wire fire taped in manholes.
R: Underground/outdoor 600V rated cable shall be single conductor wire as indicated on the conductor schedules, and rated for installation in Cable tray and/or direct burial and continuous submersion where installed in underground ducts.
18. Q: Is dual rated THHN-2 single conductor 600V wire acceptable for wire sizes larger than #6? THHN-2 dual rated 600V wire is rated for below grade use.
R: No, use cable with XHHW-2 insulation for sizes #6AWG and larger.
19. Q: Drawing 05-E-2001 indicates new electrical handholes to be 2ft x 2ft on site drawings. The handhole detail on sheet 99-E-603 show minimum of 48" required. Please clarify size required.
R: Size listed on the site drawings is for the anticipated minimum dimensions based on quantity/size of conduits. Conform to detail 2605-444 for handhole construction.

All Bidders shall acknowledge receipt and acceptance of Addendum No. 3 in the Bid Form or by submitting the Addendum with the bid package. Bid Forms submitted without acknowledgment or without this Addendum will be considered in nonconformance.

Jacobs.

David Carr, P.E.
Project Manager

Appended hereto and part of Addendum No. 3:

| | |
|--|-------------------------------|
| Proposal – Ad 3 | 40 90 00 Supplement 3 |
| 01 11 00 Summary of Work – Ad 3 | 40 90 00 Supplement 4 |
| 26 12 02B Pad-Mounted Transformers - Ad3 | 3-16 Prebid Conference agenda |
| 40 90 00 Supplement 2 | 3-16_prebid_signin_sheet |

END OF ADDENDUM

ADDENDUM NO. 3

- 8

PW\DEN003\D3887600

MARCH 24, 2026

©COPYRIGHT 2025 JACOBS

PROPOSAL

**TO: BOARD OF WATER AND SEWER COMMISSIONERS
OF THE CITY OF MOBILE, ALABAMA**

Submitted: _____
(Date)

The undersigned, as Bidder, hereby declares that he has examined the site of the Work and informed himself fully in regard to all conditions pertaining to the place where the Work is to be done; that he has examined the Plans and Specifications for the Work and all Contract Documents relative thereto, and has read the Board's Standard Specifications and all General Conditions and Special Provisions furnished; and that he has satisfied himself relative to the Work to be performed.

The Bidder proposes and agrees, if this Proposal is accepted, to contract with the Board of Water and Sewer Commissioners of the City of Mobile, Alabama, in the form of contract specified to furnish all materials, equipment, machinery, tools, apparatus, means of transportation and labor necessary to complete the following Work:

**WRIGHT SMITH JR. WWTP ELECTRICAL, I & C AND HVAC MODIFICATIONS
JACOBS PROJECT NO. D3755100**

in full and complete accordance with the shown, noted, described and reasonably intended requirements of the Plans, Specifications and all other Contract Documents to the full and entire satisfaction of the Board of Water and Sewer Commissioners of the City of Mobile, Alabama with a definite understanding that no money will be allowed for extra work except as set forth in the attached General Conditions and other Contract Documents for the lump sum or unit prices listed opposite each item.

It is agreed that the description under each item, being briefly stated, implies, although it does not mention, all incidentals and that the prices stated are intended to cover all such work, materials and incidentals as constitute Bidder's obligations as described in the Specifications and any details not specifically mentioned, but evidently included in the Contract shall be compensated for the item in which it most logically is included.

The Owner reserves the right to award the Contract to the lowest responsible and responsive Bidder. The basis of award for this project shall be based upon the Total Base Bid plus the total amount of alternates that are selected by the Owner.

As reflected by the bid schedule below, the Bidder shall include an Owner's Contingency Allowance in the amount of \$200,000.00 in the total base bid price.

Bidder will complete the work in accordance with the Contract Documents for the following price:

All work under Base Bid exclusive of Owner’s Contingency Allowance \$ _____

Owner’s Contingency Allowance: \$ 200,000.00

TOTAL LUMP SUM BASE BID (total of above and equal to total bid)

\$ _____ Dollars and _____ Cents
(words)

\$ _____
(numerals)

Alternate No 1. – Additional Asphalt Overlay (Unit Price Basis)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include additional asphalt milling and overlay of existing paved areas (concurrent with other paving operations) inclusive of all associated work as necessary to complete the milling and overlay, the Contract Price will be increased on a unit price basis of \$ _____ (numerals) per square yard in the bid quantity of 1,000 square yards for a total amount of:

_____ Dollars and _____ Cents
(words)

\$ _____
(numerals)

Alternate No 2. – Asphalt Replacement (Unit Price Basis)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include asphalt removal and replacement with 3 inches thick asphalt (concurrent with other paving operations) inclusive of all associated work as necessary to complete the replacement, the Contract Price will be increased on a unit price basis of \$ _____ (numerals) per square yard in the bid quantity of 200 square yards for a total amount of:

_____ Dollars and _____ Cents (words)

\$ _____
(numerals)

Alternate No 3. – High-Mast Light Lifting Mechanism and Fixture Bulb Replacement

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include replacement of the high-mast light lifting mechanism and all the bulbs of the light fixtures on the pole as indicated in the Drawings inclusive of all associated work as necessary to complete the replacement, the Contract Price will be increased in the amount of:

_____ Dollars and _____ Cents
(words)

\$ _____
(numerals)

Alternate No 4. – Wright Smith Jr. WWTP Entrance Sign

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include the construction of a Main Entry Sign at the Wright Smith Jr. WWTP along with any and all associated components and efforts as required to complete the work as indicated in the contract documents, the Contract Price will be increased in the amount of:

_____ Dollars and _____ Cents
(words)
\$ _____
(numerals)

Alternate No 5. – High-Mast Light Fixture Bulb Replacement (Unit Price Basis)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include replacement of high-mast light fixture bulbs on various poles as directed by the Owner inclusive of all associated work as necessary to complete the replacement, the Contract Price will be increased on a unit price basis of \$ _____ (numerals) per bulb in the bid quantity of 10 bulbs for a total amount of:

_____ Dollars and _____ Cents
(words)
\$ _____
(numerals)

Alternate No 6. –Internal Wiring and Fixture Replacement of Buildings: 10- Supervisor’s Office, 20 - Influent Lift Station, 50 - Chlorine Building and 56 - Sludge Pump and Gas General Building (Exclusive of gas compressor room)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include the rewiring of the identified structures, the Contract Price will be increased in the amount of:

_____ Dollars and _____ Cents
(words)
\$ _____
(numerals)

Alternate No 7. –Internal Wiring and Fixture Replacement of Buildings: 52- Generator Electrical, 54 – Operations, 55 - Secondary Electrical and 57 - Sludge Transfer

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include the rewiring of the identified structures, the Contract Price will be increased in the amount of:

_____ Dollars and _____ Cents
(words)
\$ _____
(numerals)

Alternate No 8. – Selected 480V Conductor Replacement (Selected Unit Price Basis)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include the replacement of selected 480V conductors within existing conduits, the Contract Price will be increased in the unit-price based amount per conductor size and type as indicated below:

| Conductor Size | Conductor Type | Unit Price | Unit | Allowance Length | Extension |
|---------------------------------------|-----------------------|-------------------|-------------|-------------------------|------------------|
| 10 AWG | GND | | LF | 1500 | |
| 12 AWG | GND | | LF | 2000 | |
| 10 AWG | THHN | | LF | 1500 | |
| 12 AWG | THHN | | LF | 2500 | |
| Total Alternate 8 w/ All Conductors = | | | | | |

Alternate No 9. – Selected 120/240 and 480V Conductor Replacement (Selected Unit Price Basis)

Bidder further proposes that if the Board of Water and Sewer Commissioners of the City of Mobile, Alabama elects to direct and include the replacement of selected 120/240 and 480V conductors within existing conduits, the Contract Price will be increased in the unit-price based amount per conductor size and type as indicated below:

| Conductor Size | Conductor Type | Unit Price | Unit Price | Allowance Length | Extension |
|---------------------------------------|-----------------------|-------------------|-------------------|-------------------------|------------------|
| 6 AWG | GND | | LF | 1000 | |
| 10 AWG | GND | | LF | 1500 | |
| 12 AWG | GND | | LF | 2500 | |
| 2/0 AWG | THHN | | LF | 4000 | |
| 8 AWG | THHN | | LF | 10000 | |
| 10 AWG | THHN | | LF | 1500 | |
| 12 AWG | THHN | | LF | 7000 | |
| #2/0 AWG | TYPE 9 | | LF | 1800 | |
| #3/0 AWG | TYPE 9 | | LF | 300 | |
| 1/0 AWG | XHHW | | LF | 1500 | |
| Total Alternate 9 w/ All Conductors = | | | | | |

The bidder attest that his bid is based upon the following manufacturer/supplier selections and changes will not be made after the bid:

(Bidder is to write in or circle the selected manufacturer or supplier)

| Section Number | Description | Manufacturer/Supplier |
|----------------|----------------------------|--------------------------------|
| 03 40 00 | Precast Building Elements | _____ (Bidder to Identify) |
| 26 29 23 | Adjustable Frequency Drive | Danfoss (Basis of Design) |
| | | Eaton Cutler Hammer |
| | | Siemens Robicon |
| | | Square D |
| 28 00 00 | Security Integrator | Security Engineering Inc. |
| | | Guardian Integrators |
| 40 90 01 | Integrator | Hargrove and Associates, LLC |
| | | Electric Machine Control, Inc. |
| | | Prime Controls, LP |
| | | Prism Systems, Inc. |
| | | Revere Control Systems, Inc. |

The Bidder further proposes and agrees hereby to commence the Work with an adequate force, plant and equipment at the time stated in the notice to the Contractor from the Engineers to proceed, and fully complete performance within 270 consecutive calendar days from and after the date stated in said notice.

The undersigned further agrees that, in case of failure on his part to execute the said Contract and the bond within 10 consecutive calendar days after written notice being given of the award of the Contract, the check or bid bond in the amount of 5 percent of this bid accompanying this bid, and the monies payable thereon, shall be paid into the funds of the Board of Water and Sewer Commissioners of the City of Mobile, Alabama as liquidated damages for such failure; otherwise the check or bid bond accompanying this Proposal shall be returned to the undersigned:

Attached hereto is a certified check on the _____
 Bank of _____ or a Bid Bond for the sum of _____
 Dollars (\$ _____)

made payable to the Board of Water and Sewer Commissioners of the City of Mobile, Alabama.

By _____

(Legal Signature)

(Printed Name and Title)

Witness: _____

(Legal Signature)

Witness: _____

(Legal Signature)

ADDRESS:

CONTRACTOR'S LICENSE NO:

BIDDER acknowledges receipt of the following ADDENDA:

**SECTION 01 11 00
SUMMARY OF WORK**

PART 1 GENERAL

1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. The completed Work will provide Owner with the components at the Wright Smith Jr. WWTP as generally enumerated as follows:
1. Replacement electrical power service, transformers, switchgear, multiple MCC's, variable frequency drives and accessories in multiple buildings.
 2. A modified SCADA system and fiber optic ring providing fiber interconnectivity to multiple buildings.
 3. New security access control, security lighting, and video security components as associated with the new facility.
 4. Two new buildings designated as the Operations Electrical Building and the Secondary Electrical Building-2.
 5. Replacement RTU's in multiple buildings.
 6. Replacement LED lighting in multiple buildings.
 7. Replacement ventilation fans, air conditioning units and accessories in multiple buildings.
 8. Additional ventilation fans and accessories in multiple buildings.
 9. Miscellaneous site/civil improvements associated with the new buildings.
- B. Alternates:
1. The Owner may accept or reject any additive alternate at its sole discretion irrespective of its acceptance of any other Additive Alternate except as indicated herein.
 2. Either or both of Additive Alternates 1 and 2 may or may not be accepted by the Owner at any time at or after the award of the Contract up to the initiation of the majority of the Project's required pavement operations at the Owner's sole discretion. The quantities of either additive alternate is at the Owner's discretion without a change in the Contract time or the unit price up to a quantity to encompass all of the existing paved areas of the facility. Unused or overages on quantities will be the basis of a change order modifying the Contract amount. The acceptance of these additive alternates will not be a basis for a change in the Contract time.
 3. Acceptance of Alternate 8 and/or 9 establishes a unit price allowance for the indicated conductor sizes up to the indicated quantities. Use of

the bid unit prices beyond those quantities shall only be at the mutual agreement of Owner and Contractor.

4. Alternates are as described below:
 - a. Alternate No. 1: Provide additional asphalt milling and overlay on a unit price basis as bid. Milling and overlay shall be of the areas as directed by the Owner and in accordance with the Contract details for milling and overlay. Where exiting pavement striping is removed, replacement striping shall be considered incidental to the replacement unit price.
 - b. Alternate No. 2: Provide asphalt replacement on a unit price basis as bid. Replacement shall be of the areas as directed by the Owner and in accordance with the specification requirements for asphalt patching. Where exiting pavement striping is removed, replacement striping shall be considered incidental to the replacement unit price.
 - c. Alternate No. 3: Provide and install replacement high-mast light lifting mechanism and full replacement of the bulbs in all the light fixtures of the pole as indicated on sheet 05-E-2002 with mechanism and bulbs as specified. NOTE: Pole lifting mechanism is currently inoperable.
 - d. Alternate No. 4: Wright Smith Jr. WWTP Entrance Sign to include the supply and construction of the entrance sign with lighting as indicated in the Drawings.
 - e. Alternate No. 5: Replace light bulbs on the fixtures on the high-mast light poles as indicted by the Owner with bulbs as specified on a per each basis inclusive of all associated work as necessary to complete the replacement.
 - f. Alternate No. 6 and Alternate No. 7: Replace all 120/240V conductors not already scheduled to be replaced where those conductors run within the same building on a lump sum basis. Replacement shall include all 120/240V switches and plugs with materials as specified within the identified buildings. Replacement conductors shall utilize the existing conduits to the fullest extent possible but shall include replacement conduit where reuse of the existing is not possible. Replacement includes any and all associated components and efforts as required to complete the Work. Where work requires the removal of batt insulation, the insulation shall be replaced with equivalent R-value insulation as a component of the bid price. Where drop-in acoustic tile ceilings are contracted for just the tiles to be replaced but the building rewiring under this alternate requires the removal of the acoustic tile grid, the grid shall be replaced in the affected rooms as a component of the respective alternate bid price. For building 56 Sludge pump and Gas Generator Building, the gas generator building is excluded from the alternate's scope of work.

- g. Alternate No. 8: Replace selected 480V conductors not already scheduled to be replaced where those conductors run within the same building. Replacement conductors shall utilize the existing conduits to the fullest extent possible but shall include replacement where reuse of the existing is not possible. Work under this unit price includes replacement any conduit seals along with any and all associated components and efforts as required to complete the installation of the new conductors. Replacements shall be of the size, type, and location as directed by the Owner with payment on a per-foot unit-price basis by conductor size and type per the bid schedule. Payment will be made based upon the actual length installed with a minimum of 30 feet per required pull as tracked by the Owner's representative.
- h. Alternate No. 9: Replace selected 120/240 and 480V conductors not already scheduled to be replaced where those conductors run from a building to the load outside the building or between loads outside a building. Replacement conductors shall utilize the existing conduits to the fullest extent possible. Where reuse of the existing conduit is not possible, Owner will provide direction on use of spare conduits or replacement as an Owner's Allowance allocation. Work under this unit price includes replacement of any conduit seals along with any and all associated components and efforts as required to complete the installation of the new conductors. Replacements shall be of the size, type, and location as directed by the Owner with payment on a per-foot unit-price basis by conductor size and type per the bid schedule. Payment will be made based upon the actual length installed with a minimum of 60 feet per required pull as tracked by the Owner's representative.
- i. A Contract time change is not associated with any of these alternates.

1.02 PROVISIONS FOR FUTURE WORK

- A. Provisions for future construction are shown on the Drawings.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 26 12 02
OIL-FILLED PAD MOUNTED TRANSFORMERS

PART 1 GENERAL

1.01 REFERENCES

- A. The following is a list of standards which may be referenced in this section:
1. ASTM International (ASTM): D3487, Standard Specification for Mineral Insulating Oil Used in Electrical Apparatus.
 2. Institute of Electrical and Electronics Engineers, Inc. (IEEE):
 - a. 386, Standard for Separable Insulated Connector Systems for Power Distribution Systems Above 600V.
 - b. C57.12.00, Standard General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers.
 - c. C57.12.22, Pad-Mounted, Compartmental-Type, Self-Cooled, Three-Phase Distribution Transformers with High-Voltage Bushings, 2,500 kVA and Smaller.
 - d. C57.12.26, Pad-Mounted, Compartmental-Type, Self-Cooled, Three-Phase Distribution Transformers for Use with Separable Insulated High Voltage Connectors.
 - e. C57.12.28, Switchgear and Transformers—Pad-Mounted Equipment, Enclosure Integrity.
 - f. C57.12.90, Standard Test Code for Liquid Immersed Distribution, Power, and Regulating Transformers.
 - g. C57.106, Guide for Acceptance and Maintenance of Insulating Oil in Equipment.
 - h. C62.11, Metal-Oxide Surge Arresters for Alternating-Current Power Circuits (>1 kV).
 3. National Electrical Manufacturers Association (NEMA):
 - a. TR 1, Transformers, Regulators, Reactors.
 - b. TP 1, Guide for Determining Energy Efficiency for Distribution Transformers.
 4. National Fire Protection Association (NFPA): 70, National Electrical Code (NEC).
 5. UL.
 6. United States Department of Energy: Code of Federal Regulations, Final Rule 10 CPR Part 431 DOE 2016 efficiency.

1.02 SUBMITTALS

A. Action Submittals:

1. Descriptive information.
2. Dimensional drawings.
3. Transformer nameplate data, including efficiency.
4. Schematic and connection diagrams.
5. Seismic anchorage and bracing drawings and cut sheets, as required by Section 01 88 15, Anchorage and Bracing.

B. Informational Submittals:

1. Seismic anchorage and bracing calculations as required by Section 01 88 15, Anchorage and Bracing.
2. Component and attachment testing seismic certificate of compliance as required by Section 01 45 33, Special Inspection, Observation, and Testing.
3. Operation and Maintenance Data: As specified in Section 01 78 23, Operation and Maintenance Data.
4. Factory test reports.

1.03 QUALITY ASSURANCE

- ### A. Design, test, and assemble in accordance with applicable standards of NEMA TR 1, IEEE C57.12.00, IEEE C57.12.22, IEEE C57.12.26, and IEEE C57.12.90.

1.04 EXTRA MATERIALS

- ### A. Furnish, tag, and box for shipment and storage and deliver prior to 90 percent Project completion the following spare parts, special tools, and materials:
1. One quart of paint to match color and quality of equipment final shop finish.
 2. One spare fuse links for each replaceable fuse size.
 3. Pentahead socket for 1/2-inch socket drive.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Eaton.
- B. Square D Co.
- C. General Electric.

2.02 GENERAL

- A. Integral Unit: Compartmental type unit consisting of transformer, oil-filled tank, and high and low voltage terminating compartments, assembled on a common structural base.
- B. Anchor Bolts: Type 316 stainless steel, sized by equipment manufacturer, and as specified in Section 05 50 00, Metal Fabrications.

2.03 TRANSFORMER

- A. kVA Rating: 2000kVA.
- B. Primary Voltage: 22.86kV line-to-line, three-phase, 60-Hz.
- C. Secondary Voltage: 480 volts, three-phase, three-wire, 60 Hz.
- D. BIL Rating:
 - 1. 125 kV BIL for 15 kV insulation class transformers.
 - 2. 30 kV BIL for secondary.
- E. Temperature Rise: 65 degrees C above 30 degrees average ambient with maximum ambient not to exceed 40 degrees C.
- F. Impedance:
 - 1. 1.35 percent minimum for transformers rated 150 kVA and less.
 - 2. 3.0 percent minimum for transformers rated 225, 300, and 500 kVA.
 - 3. 5.75 percent for transformers rated 750 kVA and above.
- G. Efficiency: Meet or exceed DOE 2016 efficiency requirements.
- H. Dielectric Coolant: Fully biodegradable, nontoxic, and nonbio-accumulating fluid, qualifying as “less flammable” per NEC 450.23; Factory Mutual Approved or UL Classified.
- I. Primary Taps:
 - 1. Full capacity, two 2-1/2 percent below and two 2-1/2 percent above, rated voltage.
 - 2. Externally operated no-load tap changer.
 - 3. Provisions for locking handle in any position.

Wright Smith WWTP Electrical, I&C, and HVAC Modifications

- J. Coil Conductors: Copper windings.
- K. Wye-wye transformers wound on five-legged or triplex cores.
- L. Sound Level: In accordance with manufacturer's standards.

2.04 ENCLOSURE

- A. In accordance with IEEE C57.12.28 requirements.
- B. Welded carbon steel transformer tank, with cooling panels when required, and lifting eyes.
- C. 12-gauge sheet steel terminal compartment enclosure having no exposed screws, bolts, or other fasteners that are externally removable.
- D. Color: Provide gray finish as approved by Engineer.

2.05 TERMINAL COMPARTMENTS

- A. General: IEEE C57.12.28, enclosed high and low voltage compartments side by side, separated by steel barrier, bolted to transformer tank.
 - 1. Doors:
 - a. Individual, full-height, air-filled.
 - b. Low voltage door with three-point latching mechanism, vault type handle, and single padlocking provision.
 - c. High voltage door fastenings inaccessible until low voltage door has been opened.
 - d. Door Bolts: Penta-head type.
 - e. Lift-off, stainless steel hinges and door stops.
 - f. Removable front sill to facilitate rolling or skidding over conduit stubs.
 - g. Recessed lock pocket, with steel door release bolt adjacent to secondary compartment door handle.
 - B. High Voltage Compartment:
 - 1. Deadfront in accordance with IEEE C57.12.26 type construction.
 - 2. Protective fuses.
 - 3. High voltage bushings.
 - 4. Transformer grounding pad.
 - 5. Surge arresters with barriers.
 - 6. Radial feed, two position sectionalizing load-break switch.

C. Low Voltage Compartment:

1. Livefront in accordance with IEEE C57.12.26 type construction.
2. Low voltage bushings.
3. Grounding pad.
4. Stainless steel equipment nameplate.
5. Liquid level gauge.
6. 1-inch upper filter press and filling plug.
7. Drain valve with sampling device.
8. Dial type thermometer.
9. Pressure relief valve.
10. Pressure relief device, self-resealing with indicator.
11. Pressure-vacuum gauge.
12. Mounting provision for current and potential transformers.
13. Nameplate.

2.06 BUSHINGS

A. High Voltage:

1. Deadfront Termination:
 - a. Universal bushing well rated at 15 kV in accordance with IEEE 386.
 - b. Bushings externally clamped and front removable.
 - c. Rated for 200 amperes continuous, 95 kV BIL.
 - d. Standoff brackets located adjacent to bushings.
 - e. Insulated Standoff Bushings: Class 15 kV, 95 kV BIL, 200 and 600 amperes, complete with EPDM rubber body, stainless steel eyebolt with brass pressure foot, and stainless steel base bracket.

B. Low Voltage:

1. Molded epoxy bushing clamped to tank with 8 hole spade type terminals.
2. Rated 150 percent of continuous full-load current, 30 kV BIL, 600 volts.
3. Internally connected neutral extending to neutral bushing.

2.07 HIGH VOLTAGE SWITCHING

- A. Internal, oil-immersed, gang-operated load-break, manually operated switches.
- B. Hot stick operated handle located in high voltage compartment.

- C. Capable of operating at full-load current.
- D. Feed Switch: Two-position, ON/OFF radial.

2.08 HIGH VOLTAGE PROTECTION

- A. Combination Oil-Immersed Bayonet Expulsion and Current Limiting Fuses:
 - 1. Accessibility:
 - a. Bayonet expulsion fuse accessible through primary compartment.
 - b. Current-limiting fuse accessible through tank handhole.
 - 2. Expulsion Fuse for Low Current Faults: Interrupting capacity of 1,800 amperes rms asymmetrical.
 - 3. Current Limiting for High Current Faults: Interrupting capacity of 50,000 amperes rms symmetrical.
 - 4. Bayonet fuse externally replaceable with hot stick.

2.09 TANK GROUNDING PADS

- A. High and Low Voltage Compartments:
 - 1. Connected together with bare No. 2/0 stranded copper conductors.
 - 2. Wye-wye high and low voltage neutrals internally connected with link and brought out to insulated low voltage bushing externally grounded to tank.
 - 3. Low voltage neutral connected to externally mounted insulating bushing in low voltage compartment and grounded to tank with removable strap.

2.10 TAP CHANGER WARNING SIGN

- A. Red laminated plastic, engraved to white core.
- B. Engrave to Read: DO NOT OPERATE WHEN TRANSFORMER ENERGIZED.
- C. Mount above tap changer handle.

2.11 FACTORY TESTS

- A. Production tests in accordance with IEEE C57.12.90 and IEEE C57.12.00, Section 8 and Table 16.
- B. Dielectric test in accordance with IEEE C57.12.26.

PART 3 EXECUTION

3.01 GENERAL

- A. Secure to mounting pads with anchor bolts.
- B. Install plumb and longitudinally in alignment with pad or adjacent building wall.
- C. Ground neutrals and enclosures in accordance with applicable codes.

3.02 ADJUSTMENTS

- A. Adjust voltage taps to obtain rated output voltage under normal operating load conditions.

END OF SECTION

**SUPPLEMENT 2
PAC AND NETWORK EQUIPMENT LIST**

| | |
|--------------|---|
| Notes | 1. This Equipment List is an estimate only; it is the responsibility of the PIC supplier to provide all components necessary for a fully functional PAC system that will meet the specifications. |
| | 2. A/R = "As Required" to meet functional requirements. |
| | 3. All decommissioned devices and patch cables shall be provided to owner as spares. |
| | 4. Provide and install new panel door nameplates for all panels modified at Smith WWTP in this project. |

| Code | Description | Qty. | Model | Manufacturer | Comments |
|-----------------|--|--------------|---------------------|--------------------------|---|
| | 58-CP-1, OPERATIONS ELECTRICAL BUILDING | | | | Provide all required ancillary PAC hardware including but not limited to module wiring connectors and 5069-FPD potential distributors (as needed) for a fully functional PAC system |
| Y321 | CompactLogix 5380 Controller with 3 MB User Memory,2 GB SD card, USB Port, Dual Ethernet Ports | 1 | 5069-L330ER | Allen Bradley | CPU |
| Y322 | CompactLogix 120VAC Power Supply (5V @ 4A) | 1 | 1769-PA4 | Allen Bradley | Power Supply |
| Y3231 | CompactLogix Discrete Input Module | 5 | 5069-IB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3232 | CompactLogix Discrete Output Module | 2 | 5069-OB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3233 | CompactLogix Analog Input Module | 3 | 5069-IF4IH | Allen Bradley | 4 isolated point module, current and voltage (18 Pin) |
| Y3234 | CompactLogix Analog Output Module | 2 | 5069-OF4IH | Allen Bradley | 4 isolated point module, current (18 Pin) |
| Y040 | Uninterruptible Power Supply | 1 | GXT5 Series | Vertiv | 1500 VA or as necessary to meet runtime requirement. Include relay card and interposing relays as necessary. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |

| Code | Description | Qty. | Model | Manufacturer | Comments |
|-----------------|--|--------------|----------------------|--------------------------|---|
| | 54-CP-1, OPERATIONS BUILDING, CONTROL ROOM | | | | Provide all required ancillary PAC hardware including but not limited to module wiring connectors and 5069-FPD potential distributors (as needed) for a fully functional PAC system |
| Y321 | CompactLogix 5380 Controller with 3 MB User Memory,2 GB SD card, USB Port, Dual Ethernet Ports | 1 | 5069-L330ER | Allen Bradley | CPU |
| Y322 | CompactLogix 120VAC Power Supply (5V @ 4A) | 1 | 1769-PA4 | Allen Bradley | Power Supply |
| Y3231 | CompactLogix Discrete Input Module | 2 | 5069-IB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3232 | CompactLogix Discrete Output Module | 1 | 5069-OB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3233 | CompactLogix Analog Input Module | 5 | 5069-IF4IH | Allen Bradley | 4 isolated point module, current and voltage (18 Pin) |
| Y3234 | CompactLogix Analog Output Module | 1 | 5069-OF4IH | Allen Bradley | 4 isolated point module, current (18 Pin) |
| Y040 | Uninterruptible Power Supply | 1 | GXT5 Series | Vertiv | 1500 VA or as necessary to meet runtime requirement. Include relay card and interposing relays as necessary. |
| Y232 | Fiber Optic Patch Panel | 1 | SPH-01P | Corning | (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing; Provide fiber jumpers |
| Y108 | Stratix-Managed Ethernet Switch (ENS-1, ENS-2) | 2 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |

| Code | Description | Qty. | Model | Manufacturer | Comments |
|-----------------|--|--------------|---------------------------------|--------------------------|---|
| | 52-CP-1, GENERATOR ELECTRICAL BUILDING | | | | Provide all required ancillary PAC hardware including but not limited to module wiring connectors and 5069-FPD potential distributors (as needed) for a fully functional PAC system |
| Y321 | CompactLogix 5380 Controller with 3 MB User Memory,2 GB SD card, USB Port, Dual Ethernet Ports | 1 | 5069-L330ER | Allen Bradley | CPU |
| Y322 | CompactLogix 120VAC Power Supply (5V @ 4A) | 1 | 1769-PA4 | Allen Bradley | Power Supply |
| Y3231 | CompactLogix Discrete Input Module | 4 | 5069-IB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3232 | CompactLogix Discrete Output Module | 1 | 5069-OB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3233 | CompactLogix Analog Input Module | 6 | 5069-IF4IH | Allen Bradley | 4 isolated point module, current and voltage (18 Pin) |
| Y3234 | CompactLogix Analog Output Module | 0 | 5069-OF4IH | Allen Bradley | 4 isolated point module, current (18 Pin) |
| Y040 | Uninterruptible Power Supply | 1 | GXT5 Series | Vertiv | 1500 VA or as necessary to meet runtime requirement. Include relay card and interposing relays as necessary. |
| Y232 | Fiber Optic Patch Panel (FOPP-1, FOPP-2) | 2 | SPH-01P | Corning | (2) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housings; Provide fiber jumpers |
| Y108 | Stratix Managed Ethernet Switch (ENS-1, ENS-2) | 2 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| Y108 | Stratix Managed Ethernet Switch (ENS-2) | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (1) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | 55-CP-1, SECONDARY ELECTRICAL BUILDING 1 | | | | Provide all required ancillary PAC hardware including but not limited to module wiring connectors and 5069-FPD potential distributors (as needed) for a fully functional PAC system |
| Y321 | CompactLogix 5380 Controller with 3 MB User Memory,2 GB SD card, USB Port, Dual Ethernet Ports | 1 | 5069-L330ER | Allen Bradley | CPU |
| Y322 | CompactLogix 120VAC Power Supply (5V @ 4A) | 1 | 1769-PA4 | Allen Bradley | Power Supply |
| Y3231 | CompactLogix Discrete Input Module | 5 | 5069-IB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3232 | CompactLogix Discrete Output Module | 2 | 5069-OB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3233 | CompactLogix Analog Input Module | 6 | 5069-IF4IH | Allen Bradley | 4 isolated point module, current and voltage (18 Pin) |
| Y3234 | CompactLogix Analog Output Module | 4 | 5069-OF4IH | Allen Bradley | 4 isolated point module, current (18 Pin) |
| Y040 | Uninterruptible Power Supply | 1 | GXT5 Series | Vertiv | 1500 VA or as necessary to meet runtime requirement. Include relay card and interposing relays as necessary. |
| Y232 | Fiber Optic Patch Panel | 1 | SPH-01P | Corning | (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing; Provide fiber jumpers |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | 60-CP-1, EFFLUENT PUMP STATION BUILDING | | | | Provide all required ancillary PAC hardware including but not limited to module wiring connectors and 5069-FPD potential distributors (as needed) for a fully functional PAC system |
| Y321 | CompactLogix 5380 Controller with 3 MB User Memory,2 GB SD card, USB Port, Dual Ethernet Ports | 1 | 5069-L330ER | Allen Bradley | CPU |
| Y322 | CompactLogix 120VAC Power Supply (5V @ 4A) | 1 | 1769-PA4 | Allen Bradley | Power Supply |
| Y3231 | CompactLogix Discrete Input Module | 4 | 5069-IB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3232 | CompactLogix Discrete Output Module | 1 | 5069-OB16 | Allen Bradley | 24VDC; 16 point module (18 Pin) |
| Y3233 | CompactLogix Analog Input Module | 2 | 5069-IF4IH | Allen Bradley | 4 isolated point module, current and voltage (18 Pin) |
| Y3234 | CompactLogix Analog Output Module | 2 | 5069-OF4IH | Allen Bradley | 4 isolated point module, current (18 Pin) |
| Y040 | Uninterruptible Power Supply | 1 | GXT5 Series | Vertiv | 1500 VA or as necessary to meet runtime requirement. Include relay card and interposing relays as necessary. |
| Y232 | Fiber Optic Patch Panel | 1 | SPH-01P | Corning | (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing; Provide fiber jumpers |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | | | | | |

| Code | Description | Qty. | Model | Manufacturer | Comments |
|------|--|------|----------------------|--------------|--|
| | SCADA NETWORK PANEL, SLUDGE PUMP & GAS BLDG | | | | Existing control panel in Sludge Pump & Gas Generation Building |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. (1) SM SFP required. |
| Y232 | Fiber Optic Patch Panel | 1 | SPH-01P | Corning | (1) CCH-CP24-E4 Connector Housing; Provide fiber jumpers |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | MCP-200, HEADWORKS SCREENING CONTROL PANEL 1 | | | | Existing vendor (package) control panel |
| Y232 | Fiber Optic Patch Panel | 1 ↗ | SPH-01P | Corning | (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing; Provide fiber jumpers. NOTE: Compact FOPPs (such as DINSpace SNAP series) also allowed. |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | DC Power Supply | 1 | | | Provide DC power to Ethernet switch. Fuse AC input and DC output. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | MCP-250, HEADWORKS SCREENING CONTROL PANEL 2 | | | | Existing vendor (package) control panel |
| Y232 | Fiber Optic Patch Panel | 1 ↗ | SPH-01P | Corning | (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing; Provide fiber jumpers. NOTE: Compact FOPPs (such as DINSpace SNAP series) also allowed. |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | DC Power Supply | 1 | | | Provide DC power to Ethernet switch. Fuse AC input and DC output. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | MCP-510, GRIT SYSTEM CONTROL PANEL 1 | | | | Existing vendor (package) control panel |
| Y232 | Fiber Optic Patch Panel | 1 ↗ | SPH-01P | Corning | (1) (2) CCH-CP12-E4 Connector Housings; Provide fiber jumpers. NOTE: Compact FOPPs (such as DINSpace SNAP series) also allowed. |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (1) (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | DC Power Supply | 1 | | | Provide DC power to Ethernet switch. Fuse AC input and DC output. |
| | | | | | |
| Code | Description | Qty. | Model | Manufacturer | Comments |
| | MCP-520, GRIT SYSTEM CONTROL PANEL 2 | | | | Existing vendor (package) control panel |
| Y232 | Fiber Optic Patch Panel | 1 ↗ | SPH-01P | Corning | (1) (2) CCH-CP12-E4 Connector Housings; Provide fiber jumpers. NOTE: Compact FOPPs (such as DINSpace SNAP series) also allowed. |
| Y108 | Stratix Managed Ethernet Switch | 1 | FortiSwitch FSR-108F | Fortinet | SCADA Field Ethernet Switch, (1) (2) MM SFP required. |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | DC Power Supply | 1 | | | Provide DC power to Ethernet switch. Fuse AC input and DC output. |
| | | | | | |

| Code | Description | Qty. | Model | Manufacturer | Comments |
|------|---|------------------------------|------------------------------------|-----------------|---|
| | SECURITY SWITCH PANEL (SWP) | 19 | | | Control panels for Security equipment fiber optic network access. See Control Panel Schedule (40 90 00, Supplement 4). See Drawing 99-TY-5002, Detail 2813-026. |
| Y232 | Fiber Optic Patch Panel | 1 2 per SWP | SPH-01P | Corning | For each SWP, also include: (1) CCH-CP24-E4 (2) CCH-CP12-E4 Connector Housing |
| | Fiber optic patch cables, Cat6 patch cables | A/R | | | Provide as necessary in appropriate lengths and specified colors. |
| | Uninterruptible Power Supply and Battery | 1 per SWP | 2907160 (UPS) 1274119 (Battery) | Phoenix Contact | See Drawing 05-TY-6002 (typical) and other Security Riser drawings. |
| | DC Power Supply | 1 per SWP | | | Provide 48 VDC power to POE Ethernet switch. Fuse AC input and DC output. |

58-PAC-1 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|-------------------|--|------|-------------------------|
| WSRTU01_XA032 | Primary Clarifiers Clarifier 2 Alarms Torque Fault | DI | New wiring from MCC 1/2 |
| WSRTU01_JI032 | Primary Clarifiers Clarifier 2 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_XA031 | Primary Clarifiers Clarifier 1 Alarms Torque Fault | DI | New wiring from MCC 1/2 |
| WSRTU01_JI031 | Primary Clarifiers Clarifier 1 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI901 | Primary Sludge & Scum Pump 4 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI902 | Primary Sludge & Scum Pump 3 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI903 | Primary Sludge & Scum Pump 2 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI904 | Primary Sludge & Scum Pump 1 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_XA033 | Primary Clarifiers Clarifier 3 Alarms Torque Fault | DI | New wiring from MCC 1/2 |
| WSRTU01_JI033 | Primary Clarifiers Clarifier 3 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI034 | Primary Clarifiers Clarifier 4 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU01_XA034 | Primary Clarifiers Clarifier 4 Alarms Torque Fault | DI | New wiring from MCC 1/2 |
| WSRTU01_JI869C | Disinfection Scrubber Fan Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI869B | Disinfection Scrubber Pump Running | DI | New wiring from MCC 1/2 |
| WSRTU01_JI869A | Disinfection Scrubber System Ready | DI | New wiring from MCC 1/2 |
| WSRTU02_QA025 | Influent PS Pump 5 Alarms VFD Fault | DI | New wiring from MCC 1/2 |
| WSRTU02_XA025A | Influent PS Pump 5 Alarms Seal Fail | DI | New wiring from MCC 1/2 |
| WSRTU02_MA021 | Influent PS Pump 1 Alarms Seal Fail | DI | New wiring from MCC 1/2 |
| WSRTU02_TA021A | Influent PS Pump 1 Alarms High Motor Temp | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI021A_IN | Influent PS Pump 1 Status VFD in AUTO | DI | New wiring from MCC 1/2 |
| WSRTU02_JI021 | Influent PS Pump 1 Status VFD Running | DI | New wiring from MCC 1/2 |
| WSRTU02_QA021 | Influent PS Pump 1 Alarms VFD Fault | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI021C | Influent PS Pump 1 Status VFD Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI021D | Influent PS Pump 1 Status Bypass Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_MA022 | Influent PS Pump 2 Alarms Seal Fail | DI | New wiring from MCC 1/2 |
| WSRTU02_TA022A_IN | Influent PS Pump 2 Alarms High Temp | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI022A_IN | Influent PS Pump 2 Status VFD in AUTO | DI | New wiring from MCC 1/2 |
| WSRTU02_JI022 | Influent PS Pump 2 Status VFD Running | DI | New wiring from MCC 1/2 |
| WSRTU02_QA022 | Influent PS Pump 2 Alarms VFD Fault | DI | New wiring from MCC 1/2 |

| | | | |
|-------------------|--|----|---|
| WSRTU02_ZI022C | Influent PS Pump 2 Status VFD Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI022D | Influent PS Pump 2 Status Bypass Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_MA023 | Influent PS Pump 3 Status High Moisture | DI | New wiring from MCC 1/2 |
| WSRTU02_TA023A_IN | Influent PS Pump 3 Status High Temp | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI023A_IN | Influent PS Pump 3 Status VFD in AUTO | DI | New wiring from MCC 1/2 |
| WSRTU02_JI023 | Influent PS Pump 3 Status VFD Running | DI | New wiring from MCC 1/2 |
| WSRTU02_QA023 | Influent PS Pump 3 Alarms VFD Fault | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI023C | Influent PS Pump 3 Status VFD Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI023D | Influent PS Pump 3 Status Bypass Mode Feedback | DI | New wiring from MCC 1/2 |
| WSRTU02_MA024 | Influent PS Pump 4 Alarms Seal Fail | DI | New wiring from MCC 1/2 |
| WSRTU02_TA024A_IN | Influent PS Pump 4 Alarms High Temp | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI024A | Influent PS Pump 4 Status VFD in AUTO | DI | New wiring from MCC 1/2 |
| WSRTU02_JI024 | Influent PS Pump 4 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU02_QA024 | Influent PS Pump 4 Alarms VFD Fault | DI | New wiring from MCC 1/2 |
| WSRTU02_JI025 | Influent PS Pump 5 Status Running | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI025A | Influent PS Pump 5 Status VFD in AUTO | DI | New wiring from MCC 1/2 |
| WSRTU02_JI092 | Post Thickener Rake Status Running | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI092 | Post-Thickener Rake Torque Fault | DI | New wiring from MCC 1/2 |
| WSRTU02_ZI021B | Influent PS Pump 1 Status Field-Remote | DI | Existing RTU-2 wiring; rewire to 58-CP-1 |
| WSRTU02_ZI022B | Influent PS Pump 2 Status Field-Remote | DI | Existing RTU-2 wiring; rewire to 58-CP-1 |
| WSRTU02_ZI023B | Influent PS Pump 3 Status Field-Remote | DI | Existing RTU-2 wiring; rewire to 58-CP-1 |
| | Influent PS Pump 4 Status Field-Remote | DI | Assumed to exist; field verify |
| WSRTU02_ZI025B | Influent PS Pump 5 Status Field-Remote | DI | Existing RTU-2 wiring; rewire to 58-CP-1 |
| | 58-CP-1 Panel Intrusion | DI | |
| | 58-CP-1 AC Power Fail | DI | |
| | 58-CP-1 DC Power Fail | DI | |
| | 58-CP-1 UPS Battery Low Alarm | DI | Provide UPS relay card; interposing relay |
| | 58-CP-1 UPS Failure Alarm | DI | Provide UPS relay card; interposing relay |
| WSRTU02_QS021A | Influent PS Pump 1 Status RunCommand | DO | New wiring from MCC 1/2 |
| WSRTU02_HS021B | Influent Pump #1 VFD Remote Drive Mode | DO | New wiring from MCC 1/2 |
| WSRTU02_HS021C | Influent Pump #1 VFD Remote Stop | DO | New wiring from MCC 1/2 |
| WSRTU02_HS021D | Influent Pump #1 VFD Remote Bypass Mode | DO | New wiring from MCC 1/2 |
| WSRTU02_QS022A | Influent PS Pump 2 Status RunCommand | DO | New wiring from MCC 1/2 |
| WSRTU02_HS022B | Influent Pump #2 VFD Remote Drive Mode | DO | New wiring from MCC 1/2 |

| | | | |
|----------------|---|----|--------------------------------|
| WSRTU02_HS022C | Influent Pump #2 VFD Remote Stop | DO | New wiring from MCC 1/2 |
| WSRTU02_HS022D | Influent Pump #2 VFD Remote Bypass Mode | DO | New wiring from MCC 1/2 |
| WSRTU02_QS023A | Influent PS Pump 3 Status RunCommand | DO | New wiring from MCC 1/2 |
| WSRTU02_HS023B | Influent Pump #3 VFD Remote Drive Mode | DO | New wiring from MCC 1/2 |
| WSRTU02_HS023C | Influent Pump #3 VFD Remote Stop | DO | New wiring from MCC 1/2 |
| WSRTU02_HS023D | Influent Pump #3 VFD Remote Bypass Mode | DO | New wiring from MCC 1/2 |
| WSRTU02_HS025A | Influent Pump #5 Run Relay | DO | New wiring from MCC 1/2 |
| WSRTU02_QS024A | Influent PS Pump 4 Status RunCommand | DO | New wiring from MCC 1/2 |
| WSRTU02_QS025 | Influent PS Pump 5 Status RunCommand | DO | New wiring from MCC 1/2 |
| WSRTU02_XI021 | Influent PS Pump 1 Motor Load | AI | New wiring from MCC 1/2 |
| WSRTU02_SIC021 | Influent PS Pump 1 Speed Feedback | AI | New wiring from MCC 1/2 |
| WSRTU02_SIC022 | Influent PS Pump 2 Speed Feedback | AI | New wiring from MCC 1/2 |
| WSRTU02_XI022 | Influent PS Pump 2 Motor Load | AI | New wiring from MCC 1/2 |
| WSRTU02_SIC023 | Influent PS Pump 3 Speed Feedback | AI | New wiring from MCC 1/2 |
| WSRTU02_XI023 | Influent PS Pump 3 Motor Load | AI | New wiring from MCC 1/2 |
| WSRTU02_SIC024 | Influent PS Pump 4 Speed Feedback | AI | New wiring from MCC 1/2 |
| WSRTU02_XI024 | Influent PS Pump 4 Motor Load | AI | New wiring from MCC 1/2 |
| WSRTU02_SIC025 | Influent PS Pump 5 Speed Feedback | AI | New wiring from MCC 1/2 |
| | Influent PS Pump 5 Motor Load | AI | Assumed to exist; field verify |
| WSRTU02_SCC021 | Influent PS Pump 1 Speed Command | AO | New wiring from MCC 1/2 |
| WSRTU02_SCC022 | Influent PS Pump 2 Speed Command | AO | New wiring from MCC 1/2 |
| WSRTU02_SCC023 | Influent PS Pump 3 Speed Command | AO | New wiring from MCC 1/2 |
| WSRTU02_SCC024 | Influent PS Pump 4 Speed Manual Cmd | AO | New wiring from MCC 1/2 |
| WSRTU02_SCC025 | Influent PS Pump 5 Speed Manual Cmd | AO | New wiring from MCC 1/2 |

54-PAC-1 (Formerly RTU-1) I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|---------------|---|------|----------|
| WSRTU01_JI027 | Splitter Box Preaerator Blower Status Running | DI | |
| WSRTU01_ZI027 | Splitter Box Preaerator Blower Command AutoMode | DI | |
| WSRTU01_JI905 | Primary Sludge & Scum Pump 5 Status Running | DI | |
| WSRTU01_JI906 | Primary Sludge & Scum Pump 6 Status Running | DI | |

| | | | |
|---------------------|--|----|---|
| WSRTU01_JI907 | Primary Sludge & Scum Pump 7 Status Running | DI | |
| WSRTU01_PAH864A | Disinfection Chlorine Vacuum #1 High | DI | |
| WSRTU01_TAH862 | Disinfection Chlorine Evaporator High Temperature | DI | |
| WSRTU01_PAH864B | Disinfection Chlorine Vacuum #2 High | DI | |
| WSRTU01_PAL864A | Disinfection Chlorine Vacuum #1 Low | DI | |
| WSRTU01_XA867 | Disinfection Chlorine CL2 Leak | DI | |
| WSRTU01_PAL864B | Disinfection Chlorine Vacuum #2 Low | DI | |
| WSRTU01_QA865 | Disinfection Chlorine CL2 Regulator Low | DI | |
| WSRTU01_QA855 | Disinfection Sulfonator SO2 Regulator Low | DI | |
| WSRTU01_XA857 | Disinfection Sulfonator SO2 Leak | DI | |
| WSRTU01_PAH854B | Disinfection Sulfonator Sulfonator #1 SO2 Vacuum High | DI | |
| WSRTU01_TAH852 | Disinfection Sulfonator SO2 Evaporator High Temp | DI | |
| WSRTU01_PAH854A | Disinfection Sulfonator Sulfonator #2 SO2 Vacuum High | DI | |
| WSRTU01_PAL854B | Disinfection Sulfonator Sulfonator #1 SO2 Vacuum Low | DI | |
| WSRTU01_PAL854A | Disinfection Sulfonator Sulfonator #2 SO2 Vacuum Low | DI | |
| WSRTU01_JI102 | Sludge Transfer Pump to Truck P1-2 Status Running | DI | |
| WSRTU01_JI101 | Sludge Transfer Pump to Truck P1-1 Status Running | DI | |
| WSRTU01_JI091 | Pre-Thickener Rake Status Running | DI | |
| WSRTU01_JI103 | Sludge Transfer Pump to Truck P1-3 Status Running | DI | |
| OFFICE_UP_TRBL | Fire Suppression Office Upstairs Fire Suppression System Trouble | DI | |
| WSRTU01_XA091 | Pre-Thickener Rake Alarms Torque Fault | DI | |
| OFFICE_UP_ALM | Fire Suppression Office Upstairs Fire Suppression System Alarm | DI | |
| OFFICE_DN_TRBL | Fire Suppression Office Downstairs Fire Suppression System Trouble | DI | |
| OFFICE_DN_ALM | Fire Suppression Office Downstairs Fire Suppression System Alarm | DI | |
| | 54-CP-1 Panel Intrusion | DI | |
| | 54-CP-1 AC Power Fail | DI | |
| | 54-CP-1 DC Power Fail | DI | |
| | 54-CP-1 UPS Battery Low Alarm | DI | Provide UPS relay card; interposing relay |
| | 54-CP-1 UPS Failure Alarm | DI | Provide UPS relay card; interposing relay |
| WSRTU01_HC027 | Splitter Box Preaerator Blower Status RunCommand | DO | |
| WSRTU01_QS861A | Remote Switch For CL2 Field Controller | DO | Deleted - Field Verify |
| WSRTU01_QS850 | Remote Switch For SO2 Field Controller | DO | Deleted - Field Verify |
| WSRTU01_OPENGATECMD | Unused | DO | Field Verify |
| WSRTU01_FI033 | Primary Sludge & Scum Flow | AI | |

| | | | |
|-----------------|--|----|------------------------|
| WSRTU01_ZI861A | Disinfection Chlorine CL2 Flow | AI | |
| WSRTU01_WT868B | Disinfection Sulfonator SO2 Scale 2 Weight | AI | |
| WSRTU01_WT868D | Disinfection Chlorine CL2 Scale 2 Weight | AI | |
| WSRTU01_FI005 | Sludge Transfer Truck Loading Flow | AI | |
| WSRTU01_FI034 | Primary Sludge & Scum Flow 2 | AI | |
| WSRTU01_WT868A | Disinfection Sulfonator SO2 Scale 1 Weight | AI | |
| WSRTU01_WT868C | Disinfection Chlorine CL2 Scale 1 Weight | AI | |
| WSRTU01_ZI850 | Disinfection Sulfonator SO2 Valve Position | AI | |
| WSRTU01_FI081 | Pre-Thickener P95 Flow | AI | |
| WSRTU01_LI040 | Pre-Thickener Sludge Blanket Level | AI | |
| WSRTU01_FI007 | Gas Flows Waste Gas Flow | AI | |
| WSRTU01_FI122 | Gas Flows Influent Gas Flow | AI | |
| WSRTU01_FI082 | Pre-Thickener P96 Flow | AI | |
| WSRTU01_RIC861A | Cl2 Ratio Set | AO | Deleted - Field Verify |
| WSRTU01_RIC850 | SO2 Ratio Set | AO | Deleted - Field Verify |

52-PAC-1 (Formerly RTU-2) I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|-----------------|---|------|------------------------|
| WSRTU02_JI030 | Electrical RTU2 Phase Failure | DI | To be deleted |
| WSRTU02_LAH011D | Head Works Side #1 Level High | DI | Deleted - Field Verify |
| WSRTU02_JI011 | Headworks Right Side (#1) Climb Screen Status Running | DI | Deleted - Field Verify |
| WSRTU02_JI012 | Headworks Left Side (#2) Climb Screen Status Running | DI | Deleted - Field Verify |
| WSRTU02_LAH012D | Headworks Right Side Level High | DI | Deleted - Field Verify |
| WSRTU02_ZI016 | Headworks Conveyer Command AutoMode | DI | Deleted - Field Verify |
| WSRTU02_ZI017 | Preaerator Blower 1 Command AutoMode | DI | Deleted - Field Verify |
| WSRTU02_JI017 | Preaerator Blower 1 Status Running | DI | Deleted - Field Verify |
| WSRTU02_ZI019 | Preaerator Blower 3 Command AutoMode | DI | Deleted - Field Verify |
| WSRTU02_JI019 | Preaerator Blower 3 Status Running | DI | Deleted - Field Verify |
| WSRTU02_XA025B | | DI | Deleted - Field Verify |
| WSRTU02_JI018 | Preaerator Blower 2 Status Running | DI | Deleted - Field Verify |

| | | | |
|----------------------|---|----|--|
| WSRTU02_ZI018 | Preaerator Blower 2 Command AutoMode | DI | Deleted - Field Verify |
| WSRTU02_JI035 | Electrical Generator Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_XA035 | Electrical Generator General Alarm | DI | Wiring from 52-TJB-1 |
| WSRTU02_QI021B | Influent PS Low Float - Pump Enable | DI | Wiring from 52-TJB-1 |
| WSRTU02_LA021A_IN | Influent PS Wet Well Level Transmitter Failure | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI025OLD | | DI | Deleted - Field Verify |
| WSRTU02_ZI025OLD | | DI | Deleted - Field Verify |
| WSRTU02_LAH021A | Influent PS Pumps Dry Well High Level | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI095 | Pre-Thickener Pumps P95 Status Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_ZI095 | Pre-Thickener Pumps P95 Status Field-Remote | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI096 | Pre-Thickener Pumps P96 Status Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_ZI096 | Pre-Thickener Pumps P96 In Auto | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI122 | Digesters Heat Exchangers Hot Water Pump #2 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI121 | Digesters Heat Exchangers Hot Water Pump #1 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_LLI050 | Digesters Heat Exchangers Hot Water Make Up Tank Low Level | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI047 | Digesters Sludge Recirc P112 Status Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_ZI047 | Digesters Sludge Recirc P112 Status MCC-Remote | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI048 | Digesters Sludge Recirc P113 Status Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_ZI048 | Digesters Sludge Recirc P113 Status MCC-Remote | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI111 | Digesters Mixing Gas Compressor #1 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI112 | Digesters Mixing Gas Compressor #2 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI113 | Digesters Mixing Gas Compressor #3 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI114 | Digesters Mixing Gas Compressor #4 Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI046 | Digesters Sludge Recirc P111 Status Running | DI | Wiring from 52-TJB-1 |
| WSRTU02_ZI046 | Digesters Sludge Recirc P111 Status MCC-Remote | DI | Wiring from 52-TJB-1 |
| WSRTU02_JI115 | Digesters Heat Exchangers Gas Boiler Running | DI | Wiring from 52-TJB-1 |
| RTU2_TRBL | Fire Suppression Generator Building Fire Suppression System Trouble | DI | Wiring from 52-TJB-1 |
| RTU2_ALM | Fire Suppression Generator Building Fire Suppression System Alarm | DI | Wiring from 52-TJB-1 |
| WSRTU2_PS1_OK | Electrical RTU2 Power Supply 1 Fault | DI | To be deleted |
| WSRTU2_PS2_OK | Electrical RTU2 Power Supply 2 Fault | DI | To be deleted |
| WSRTU02_FQI100_PULSE | Influent Flow Totalizer Pulse | DI | Wiring from 52-TJB-1 |
| WSRTU02_FQI110_PULSE | Band Screen Channel Flow Totalizer Pulse | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_LSH110 | Band Screen Channel High Level Float | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_SCRN110_ON | Band Screen Running | DI | Deleted - Field Verify Wiring from 52-TJB-1 |

| | | | |
|-----------------------|--|----|--|
| WSRTU02_SCRN110_FAIL | Band Screen Fail | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_SCRN110_ESTOP | Band Screen Estopped | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_SCRN120_ON | Band Screen Press Running | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_SCRN120_FAIL | Band Screen Press Fail | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_P130_ON | Band Screen Wash Water Pump Running | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| WSRTU02_P130_FAIL | Band Screen Wash Water Pump Fail | DI | Deleted - Field Verify Wiring from 52-TJB-1 |
| | 52-CP-1 Panel Intrusion | DI | |
| | 52-CP-1 AC Power Fail | DI | |
| | 52-CP-1 DC Power Fail | DI | |
| | 52-CP-1 UPS Battery Low Alarm | DI | Provide UPS relay card; interposing relay |
| | 52-CP-1 UPS Failure Alarm | DI | Provide UPS relay card; interposing relay |
| WSRTU02_HS110 | Grit Remover Status RunCommand | DO | |
| WSRTU02_HS017 | Preaerator Blower 1 Status RunCommand | DO | Deleted - Field Verify |
| WSRTU02_HS019 | Preaerator Blower 3 Status RunCommand | DO | Deleted - Field Verify |
| WSRTU02_HS018 | Preaerator Blower 2 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_HC095 | Pre-Thickener Pumps P95 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_HC096 | Pre-Thickener Pumps P96 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_HS046 | Digesters Sludge Recirc P111 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_HS047 | Digesters Sludge Recirc P112 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_HS048 | Digesters Sludge Recirc P113 Status RunCommand | DO | Wiring from 52-TJB-1 |
| WSRTU02_LI011A | Headworks Differential Level Left Side | AI | Deleted - Field Verify |
| WSRTU02_LI012 | Headworks Differential Level Right Side | AI | Deleted - Field Verify |
| WSRTU02_LI011B | Headworks Level A | AI | Deleted - Field Verify |
| WSRTU02_LI012B | Headworks Level B | AI | Deleted - Field Verify |
| WSRTU02_XI035_RAW | Influent Generator Amps | AI | Wiring from 52-TJB-1 |
| WSRTU02_LIC021 | Influent PS Wet Well Level | AI | Wiring from 52-TJB-1 |
| INFLUENT_FLOW | WS Influent Flow | AI | Deleted - Field Verify |
| WSRTU02_LT3000 | | AI | Deleted - Field Verify |
| WSRTU02_LT4000 | | AI | Deleted - Field Verify |
| WSRTU02_TI042 | Digesters Digester 1 Sludge Temperature | AI | Wiring from 52-TJB-1 |
| WSRTU02_TI043 | Digesters Digester 2 Sludge Temperature | AI | Wiring from 52-TJB-1 |
| WSRTU02_TI045 | Digesters Digester 2 Temperature | AI | Wiring from 52-TJB-1 |
| WSRTU02_TI044 | Digesters Digester 1 Temperature | AI | Wiring from 52-TJB-1 |
| WSRTU02_LI110A | Band Screen Upstream Level | AI | Deleted - Field Verify Wiring from 52-TJB-1 |

| | | | |
|----------------|------------------------------|----|--|
| WSRTU02_LI110B | Band Screen Downstream Level | AI | Deleted—Field Verify Wiring from 52-TJB-1 |
| WSRTU02_FIT100 | Influent PS Sewage Flow | AI | Wiring from 52-TJB-1 |
| WSRTU02_FIT200 | Headworks Discharge Flow | AI | Wiring from 52-TJB-1 |
| WSRTU02_FIT110 | Band Screen Channel Flow | AI | Deleted—Field Verify Wiring from 52-TJB-1 |
| WSRTU02_XI025 | Electrical MCC1 Amps | AI | To be deleted |

55-PAC-1 (Formerly RTU-3) I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|-------------------|---|------|---|
| WSRTU03_JI043 | Intermediate Clarifiers Rake 3 Status Running | DI | AKA Intermediate Clarifier 1; New wiring from MCC 6/7 |
| WSRTU03_XA043 | Intermediate Clarifiers Rake 3 Alarms Starter Fault | DI | AKA Intermediate Clarifier 1; New wiring from MCC 6/7 |
| WSRTU03_JI044 | Intermediate Clarifiers Rake 4 Status Running | DI | AKA Intermediate Clarifier 2; New wiring from MCC 6/7 |
| WSRTU03_XA044 | Intermediate Clarifiers Rake 4 Alarms Starter Fault | DI | AKA Intermediate Clarifier 2; New wiring from MCC 6/7 |
| WSRTU03_ZI037 | Recycle Pump 1 Status Field-Remote | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI037 | Recycle Pump 1 Status Running | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_XA037 | Recycle Pump 1 Alarms VFD Fault | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI038 | Recycle Pump 2 Status Field-Remote | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI038 | Recycle Pump 2 Status Running | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_XA038 | Recycle Pump 2 Alarms VFD Fault | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI039 | Recycle Pump 3 Status Field-Remote | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI039 | Recycle Pump 3 Status Running | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_XA039 | Recycle Pump 3 Alarms VFD Fault | DI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI051A_IN | Secondary LS Pump 3 Status VFD in AUTO | DI | New wiring from MCC 6/7 |
| WSRTU03_JI051 | Secondary LS Pump 3 Status VFD Running | DI | New wiring from MCC 6/7 |
| WSRTU03_XA051 | Secondary LS Pump 3 Alarms VFD Fault | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI051B | Secondary Pump #3 VFD In Remote | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI051C | Secondary Pump #3 VFD Drive Mode | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI051D | Secondary LS Pump 3 Status Bypass Running | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI052A_IN | Secondary LS Pump 2 Status VFD in AUTO | DI | New wiring from MCC 6/7 |
| WSRTU03_JI052 | Secondary LS Pump 4 Status VFD Running | DI | New wiring from MCC 6/7 |
| WSRTU03_XA052 | Secondary LS Pump 4 Alarms VFD Fault | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI052B | Secondary LS Pump #4 VFD In Remote | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI052C | Secondary LS Pump #4 VFD Drive Mode | DI | New wiring from MCC 6/7 |

| | | | |
|-------------------|--|----|---|
| WSRTU03_ZI052D | Secondary LS Pump 4 Status Bypass Running | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI053A_IN | Secondary LS Pump 3 Status VFD in AUTO | DI | New wiring from MCC 6/7 |
| WSRTU03_JI053 | Secondary LS Pump 1 Status Running | DI | New wiring from MCC 6/7 |
| WSRTU03_XA053 | Secondary LS Pump 1 Alarms VFD Fault | DI | New wiring from MCC 6/7 |
| WSRTU03_ZI054A_IN | Secondary LS Pump 4 Status VFD in AUTO | DI | New wiring from MCC 6/7 |
| WSRTU03_JI054 | Secondary LS Pump 2 Status Running | DI | New wiring from MCC 6/7 |
| WSRTU03_XA054 | Secondary LS Pump 2 Alarms VFD Fault | DI | New wiring from MCC 6/7 |
| WSRTU03_JI061 | Nitrification Recirc. Pump 1 Status Running | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI061 | Nitrification Recirc. Pump 1 Command AutoMode | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI062 | Nitrification Recirc. Pump 2 Status Running | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI062 | Nitrification Recirc. Pump 2 Command AutoMode | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI063 | Nitrification Recirc. Pump 3 Status Running | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI063 | Nitrification Recirc. Pump 3 Command AutoMode | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_JI064 | Nitrification Recirc. Pump 4 Status Running | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_ZI064 | Nitrification Recirc. Pump 4 Command AutoMode | DI | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_XA051B | Secondary LS Pumps Wet Well Transmitter Fail | DI | Wiring from 55-TJB-1 |
| RTU3_TRBL | Fire Suppression RTU3 Building Fire Suppression System Trouble | DI | Wiring from 55-TJB-1 |
| RTU3_ALM | Fire Suppression RTU3 Building Fire Suppression System Alarm | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI041A | Secondary Clarifier #1 Actuator In Auto | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI036A | Secondary Clarifier #2 Actuator In Auto | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI011A | Final Clarifier Valves Discharge Valve 1 Status Field-Remote | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI012A | Final Clarifier Valves Discharge Valve 2 Status Field-Remote | DI | Wiring from 55-TJB-1 |
| WSRTU03_JI081 | Post-Aeration Mixer 1 Status Running | DI | Wiring from 55-TJB-1 |
| WSRTU03_JI082 | Post-Aeration Mixer 2 Status Running | DI | Wiring from 55-TJB-1 |
| WSRTU03_JI083 | Reuse Water Pump #1 Running | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI083 | Reuse Water Pump #1 In Auto | DI | Wiring from 55-TJB-1 |
| WSRTU03_JI084 | Reuse Water Pump 2 Status Running | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI084 | Reuse Water Pump 2 Command AutoMode | DI | Wiring from 55-TJB-1 |
| WSRTU03_QI051B | Secondary LS Low Float | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI101 | Trickle Filters Discharge Valve 1 Status Field-Remote | DI | Wiring from 55-TJB-1 |
| WSRTU03_ZI102 | Trickle Filters Discharge Valve 2 Status Field-Remote | DI | Wiring from 55-TJB-1 |
| WSRTU02_JI071 | Final Clarifier Rakes Rake 1 Status Running | DI | Existing RTU-2 wiring; New wiring from MCC 6/7 |
| WSRTU02_XA071 | Final Clarifier Rakes Rake 1 Alarms Starter Fault | DI | Existing RTU-2 wiring; New wiring from MCC 6/7 |
| WSRTU02_JI072 | Final Clarifier Rakes Rake 2 Final Clarifier Rake #2 Running | DI | Existing RTU-2 wiring; New wiring from MCC 6/7 |

| | | | |
|----------------|---|----|--|
| WSRTU02_XA072 | Final Clarifier Rakes Rake 2 Alarms Starter Fault | DI | Existing RTU-2 wiring; New wiring from MCC 6/7 |
| | 55-CP-1 Panel Intrusion | DI | |
| | 55-CP-1 AC Power Fail | DI | |
| | 55-CP-1 DC Power Fail | DI | |
| | 55-CP-1 UPS Battery Low Alarm | DI | Provide UPS relay card; interposing relay |
| | 55-CP-1 UPS Failure Alarm | DI | Provide UPS relay card; interposing relay |
| | Diesel Pump (at Secondary Pump Station) Run Status | DI | New wiring to onsite diesel pump |
| | Diesel Pump (at Secondary Pump Station) Common Alarm | DI | New wiring to onsite diesel pump |
| WSRTU03_HC037A | Recycle Pump 1 Status RunCommand | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_HC037B | Recycle Pump #1 Stop | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_HC038A | Recycle Pump 2 Status RunCommand | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_HC038B | Recycle Pump #2 Stop | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_HC039A | Recycle Pump 3 Status RunCommand | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_HC039B | Recycle Pump #3 Stop | DO | AKA Launder Recirc Pump; Wiring from MCC 6/7 |
| WSRTU03_QS051A | Secondary LS Pump 3 Status RunCommand | DO | New wiring from MCC 6/7 |
| WSRTU03_JY051B | Secondary Pump #3 VFD Remote Drive Mode | DO | New wiring from MCC 6/7 |
| WSRTU03_JY051C | Secondary Pump #3 VFD Remote Stop | DO | New wiring from MCC 6/7 |
| WSRTU03_JY051D | Secondary Pump #3 VFD Remote Bypass Mode | DO | New wiring from MCC 6/7 |
| WSRTU03_QS052A | Secondary LS Pump 4 Status RunCommand | DO | New wiring from MCC 6/7 |
| WSRTU03_JY052B | Secondary Pump #4 VFD Remote Drive Mode | DO | New wiring from MCC 6/7 |
| WSRTU03_JY052C | Secondary Pump #4 VFD Remote Stop | DO | New wiring from MCC 6/7 |
| WSRTU03_JY052D | Secondary Pump #4 VFD Remote Bypass Mode | DO | New wiring from MCC 6/7 |
| WSRTU03_QS053A | Secondary LS Pump 1 Status RunCommand | DO | New wiring from MCC 6/7 |
| WSRTU03_QS054A | Secondary LS Pump 2 Status RunCommand | DO | New wiring from MCC 6/7 |
| WSRTU03_HS061 | Nitrification Recirc. Pump 1 Status RunCommand | DO | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_HS062 | Nitrification Recirc. Pump 2 SS | DO | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_HS063 | Nitrification Recirc. Pump 3 Status RunCommand | DO | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_HS064 | Nitrification Recirc. Pump 4 Status RunCommand | DO | AKA Filter Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_HS083 | Reuse Water Pump 1 SS | DO | Wiring from 55-TJB-1 |
| WSRTU03_HS084 | Reuse Water Pump 2 SS | DO | Wiring from 55-TJB-1 |
| | Diesel Pump (at Secondary Pump Station) Run Command | DI | New wiring to onsite diesel pump |
| WSRTU03_ZI036 | Intermediate Clarifiers Discharge Valve 2 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_FI035 | Recycle Flow | AI | Wiring from 55-TJB-1 |
| WSRTU03_SIC037 | Recycle Pump 1 Speed Feedback | AI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |

| | | | |
|----------------|--|----|--|
| WSRTU03_SIC038 | Recycle Pump 2 Speed Feedback | AI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_SIC039 | Recycle Pump 3 Speed Feedback | AI | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_SIC051 | Secondary LS Pump 3 Speed Feedback | AI | New wiring from MCC 6/7 |
| WSRTU03_LIC051 | Secondary LS Pumping Station Level | AI | Wiring from 55-TJB-1 |
| WSRTU03_SIC052 | Secondary LS Pump 4 Speed Feedback | AI | New wiring from MCC 6/7 |
| WSRTU03_SIC053 | Secondary LS Pump 1 Speed Feedback | AI | New wiring from MCC 6/7 |
| WSRTU03_SIC054 | Secondary LS Pump 2 Speed Feedback | AI | New wiring from MCC 6/7 |
| WSRTU03_FI071 | Disinfection Flow CCC Flow | AI | Wiring from 55-TJB-1 |
| WSRTU03_XI851 | Post-Aeration CL2 Analyzer | AI | Wiring from 55-TJB-1 |
| WSRTU03_XI850 | Post-Aeration SO2 Analyzer | AI | Wiring from 55-TJB-1 |
| WSRTU03_ZI041 | Intermediate Clarifiers Discharge Valve 1 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_ZT101 | Trickle Filters Discharge Valve 1 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_ZT102 | Trickle Filters Discharge Valve 2 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_ZI011B | Final Clarifier Valves Discharge Valve 1 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_ZI012B | Final Clarifier Valves Discharge Valve 2 Position Feedback | AI | Wiring from 55-TJB-1 |
| WSRTU03_HIC041 | Intermediate Clarifiers Discharge Valve 1 Commanded Position | AO | Wiring from 55-TJB-1 |
| WSRTU03_HIC036 | Intermediate Clarifiers Discharge Valve 2 Commanded Position | AO | Wiring from 55-TJB-1 |
| WSRTU03_SCC037 | Recycle Pump #1 VFD Speed SP | AO | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_SCC038 | Recycle Pump #2 VFD Speed SP | AO | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_SCC039 | Recycle Pump #3 VFD Speed SP | AO | AKA Launder Recirc Pump; New wiring from MCC 6/7 |
| WSRTU03_SCC051 | Secondary Pump #3 VFD Speed SP | AO | New wiring from MCC 6/7 |
| WSRTU03_SCC052 | Secondary Pump #4 VFD Speed SP | AO | New wiring from MCC 6/7 |
| WSRTU03_SCC053 | Secondary Pump #1 VFD Speed SP | AO | New wiring from MCC 6/7 |
| WSRTU03_SCC054 | Secondary Pump #2 VFD Speed SP | AO | New wiring from MCC 6/7 |
| WSRTU03_HIC012 | Final Clarifier Valves Discharge Valve 2 Commanded Position | AO | Wiring from 55-TJB-1 |
| WSRTU03_HIC101 | Trickle Filters Discharge Valve 1 Commanded Position | AO | Wiring from 55-TJB-1 |
| WSRTU03_HIC102 | Trickle Filters Discharge Valve 2 Commanded Position | AO | Wiring from 55-TJB-1 |
| WSRTU03_HIC011 | Final Clarifier Valves Discharge Valve 1 Commanded Position | AO | Wiring from 55-TJB-1 |

60-PAC-1 (Formerly RTU-5) I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|--------------------|---------------------------------|------|----------|
| WSRTU05_GENRUNNING | Effluent Area Generator Running | DI | |

| | | | |
|-------------------------|-------------------------------------|----|--|
| WSRTU05_GENALARM | Effluent Area Generator Alarm | DI | |
| WSRTU05_ATSGEN | Effluent Area Generator ATS on GEN | DI | |
| WSRTU05_ATSUTILITY | Effluent Area Generator ATS on UTIL | DI | |
| WSRTU05_ATSAUTO | Effluent Area Generator ATS AUTO | DI | |
| WSRTU05_ATSALARM | Effluent Area Generator ATS Alarm | DI | |
| WSRTU05_FIRESUPSYS | Effluent Area Fire Supp Active | DI | |
| WSRTU05_WETWELLHIGHLVL | Effluent Wet Well High Level Float | DI | |
| WSRTU05_RESET | Reset Pushbutton | DI | |
| WSRTU05_FAULTDRIVE1 | Effluent Pump 1 VFD Fault | DI | |
| WSRTU05_FAULTDRIVE2 | Effluent Pump 2 VFD Fault | DI | |
| WSRTU05_FAULTDRIVE3 | Effluent Pump 3 VFD Fault | DI | |
| WSRTU05_FAULTDRIVE4 | Effluent Pump 4 VFD Fault | DI | |
| WSRTU05_FAULTDRIVE5 | Effluent Pump 5 VFD Fault | DI | |
| WSRTU05_CHKVLV1 | Effluent Pump 1 Check Valve Closed | DI | |
| WSRTU05_CHKVLV2 | Effluent Pump 2 Check Valve Closed | DI | |
| WSRTU05_CHKVLV3 | Effluent Pump 3 Check Valve Closed | DI | |
| WSRTU05_CHKVLV4 | Effluent Pump 4 Check Valve Closed | DI | |
| WSRTU05_CHKVLV5 | Effluent Pump 5 Check Valve Closed | DI | |
| WSRTU05_VFDRUN1 | Effluent Pump 1 VFD Running | DI | |
| WSRTU05_VFDRUN2 | Effluent Pump 2 VFD Running | DI | |
| WSRTU05_VFDRUN3 | Effluent Pump 3 VFD Running | DI | |
| WSRTU05_VFDRUN4 | Effluent Pump 4 VFD Running | DI | |
| WSRTU05_VFDRUN5 | Effluent Pump 5 VFD Running | DI | |
| WSRTU05_VFDBYPASS1 | Effluent Pump 1 VFD Bypassed | DI | |
| WSRTU05_VFDBYPASS2 | Effluent Pump 2 VFD Bypassed | DI | |
| WSRTU05_VFDBYPASS3 | Effluent Pump 3 VFD Bypassed | DI | |
| WSRTU05_VFDBYPASS4 | Effluent Pump 4 VFD Bypassed | DI | |
| WSRTU05_VFDBYPASS5 | Effluent Pump 5 VFD Bypassed | DI | |
| WSRTU05_VFDHOOAUTO1 | Effluent Pump 1 HOA in AUTO | DI | |
| WSRTU05_VFDHOOAUTO2 | Effluent Pump 2 HOA in AUTO | DI | |
| WSRTU05_VFDHOOAUTO3 | Effluent Pump 3 HOA in AUTO | DI | |
| WSRTU05_VFDHOOAUTO4 | Effluent Pump 4 HOA in AUTO | DI | |
| WSRTU05_VFDHOOAUTO5 | Effluent Pump 5 HOA in AUTO | DI | |
| WSRTU05_VFDSPDSELSWTCH1 | Effluent Pump 1 Speed Select Switch | DI | |

| | | | |
|----------------------------|--|----|---|
| WSRTU05_VFDSPDSELSWTCH2 | Effluent Pump 2 Speed Select Switch | DI | |
| WSRTU05_VFDSPDSELSWTCH3 | Effluent Pump 3 Speed Select Switch | DI | |
| WSRTU05_VFDSPDSELSWTCH4 | Effluent Pump 4 Speed Select Switch | DI | |
| WSRTU05_VFDSPDSELSWTCH5 | Effluent Pump 5 Speed Select Switch | DI | |
| WSRTU05_PHASEFAILRELAY | Effluent Pump CP Power Fail | DI | |
| WSRTU05_DIESELMONLEAK | Effluent Area Gen Fuel Leak | DI | |
| WSRTU05_DIESELMONPWRFAIL | Effluent Area Gen Fuel System Power Fail | DI | |
| WSRTU05_DIESELMONWATERLEAK | Effluent Area Gen Water In Fuel | DI | |
| WSRTU05_DIESELMONGENALARM | Effluent Area Gen Fuel Alarm | DI | |
| WSRTU05_Pmp1DiscOn | Effluent Pump 1 Disconnect On | DI | |
| WSRTU05_Pmp2DiscOn | Effluent Pump 2 Disconnect On | DI | |
| WSRTU05_Pmp3DiscOn | Effluent Pump 3 Disconnect On | DI | |
| WSRTU05_Pmp4DiscOn | Effluent Pump 4 Disconnect On | DI | |
| WSRTU05_Pmp5DiscOn | Effluent Pump 5 Disconnect On | DI | |
| WSRTU05_AerationRunning | | DI | Field verify signal. |
| WSRTU05_WaterPumpRunning | | DI | Field verify signal. |
| WSRTU05_LSL506 | Effluent Wet Well Low Level Float | DI | |
| | 60-CP-1 Panel Intrusion | DI | Add panel intrusion switch if necessary |
| | 60-CP-1 AC Power Fail | DI | Add power fail relay if necessary |
| | 60-CP-1 DC Power Fail | DI | Add power fail relay(s) if necessary |
| | 60-CP-1 UPS Battery Low Alarm | DI | Provide UPS relay card; interposing relay |
| | 60-CP-1 UPS Failure Alarm | DI | Provide UPS relay card; interposing relay |
| WSRTU05_VFDRUNCMD1_I | Effluent Pump 1 VFD Run Command | DO | |
| WSRTU05_VFDRUNCMD2_I | Effluent Pump 2 VFD Run Command | DO | |
| WSRTU05_VFDRUNCMD3_I | Effluent Pump 3 VFD Run Command | DO | |
| WSRTU05_VFDRUNCMD4_I | Effluent Pump 4 VFD Run Command | DO | |
| WSRTU05_VFDRUNCMD5_I | Effluent Pump 5 VFD Run Command | DO | |
| WSRTU05_VFDSPDFB1 | Effluent Pump 1 VFD Speed Feedback | AI | |
| WSRTU05_VFDSPDFB3 | Effluent Pump 3 VFD Speed Feedback | AI | |
| WSRTU05_VFDSPDFB4 | Effluent Pump 4 VFD Speed Feedback | AI | |
| WSRTU05_VFDSPDFB5 | Effluent Pump 5 VFD Speed Feedback | AI | |
| WSRTU05_VFDSPDFB2 | Effluent Pump 2 VFD Speed Feedback | AI | |
| WSRTU05_WETWELLLVL | Effluent Wet Well Level | AI | |
| WSRTU05_VFDRUNCMD1 | Effluent Pump 1 VFD Speed Command | AO | |

| | | | |
|--------------------|-----------------------------------|----|--|
| WSRTU05_VFDRUNCMD2 | Effluent Pump 2 VFD Speed Command | AO | |
| WSRTU05_VFDRUNCMD3 | Effluent Pump 3 VFD Speed Command | AO | |
| WSRTU05_VFDRUNCMD4 | Effluent Pump 4 VFD Speed Command | AO | |
| WSRTU05_VFDRUNCMD5 | Effluent Pump 5 VFD Speed Command | AO | |

MCP-200 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|----------------------|---|------|-------------------------|
| WSRTU02_SCRN200A_REM | Headworks Screen 1 Status Field-Remote | DI | Via New Control Network |
| WSRTU02_SCRN200A_ON | Headworks Screen 1 Status Running | DI | Via New Control Network |
| WSRTU02_SCRN200A_ALM | Headworks Screen 1 Alarms Common Alarm | DI | Via New Control Network |
| WSRTU02_LSH200 | Headworks Screen 1 Alarms Alarm Word Channel Level High | DI | Via New Control Network |
| WSRTU02_SCRN200B_REM | Headworks Screen 1 Press Status LOR-Status | DI | Via New Control Network |
| WSRTU02_SCRN200B_ON | Headworks Screen 1 Press Status Running | DI | Via New Control Network |
| WSRTU02_SCRN200_ALM | Headworks Screen 1 Alarms Alarm | DI | Via New Control Network |
| WSRTU02_HS200 | Headworks Screen 1 Start Cycle Output | DO | Via New Control Network |
| WSRTU02_LI201A | Headworks Screen 1 Upstream Level | AI | Via New Control Network |
| WSRTU02_LI201B | Headworks Screen 1 Downstream Level | AI | Via New Control Network |

MCP-250 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|----------------------|---|------|-------------------------|
| WSRTU02_SCRN250A_REM | Headworks Screen 2 Status Field-Remote | DI | Via New Control Network |
| WSRTU02_SCRN250A_ON | Headworks Screen 2 Status Running | DI | Via New Control Network |
| WSRTU02_SCRN250A_ALM | Headworks Screen 2 Press Alarms Common Alarm | DI | Via New Control Network |
| WSRTU02_LSH250 | Headworks Screen 2 Alarms Alarm Word Channel Level High | DI | Via New Control Network |
| WSRTU02_SCRN250B_REM | Headworks Screen 2 Press Status LOR-Status | DI | Via New Control Network |
| WSRTU02_SCRN250B_ON | Headworks Screen 2 Press Status Running | DI | Via New Control Network |
| WSRTU02_SCRN250B_ALM | Headworks Screen 2 Press Alarms Common Alarm | DI | Via New Control Network |
| WSRTU02_HS250 | Headworks Screen 2 Start Cycle Output | DO | Via New Control Network |
| WSRTU02_LI251A | Headworks Screen 2 Upstream Level | AI | Via New Control Network |

| | | | |
|----------------|-------------------------------------|----|-------------------------|
| WSRTU02_LI251B | Headworks Screen 2 Downstream Level | AI | Via New Control Network |
|----------------|-------------------------------------|----|-------------------------|

MCP-510 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|----------------|----------------------------------|------|-------------------------|
| WSRTU02_JI510A | Grit Pump 1 Status Running | DI | Via New Control Network |
| WSRTU02_QA510A | Grit Pump 1 Alarms Starter Fault | DI | Via New Control Network |
| WSRTU02_ZI510A | Grit Pump 1 Status LOR-Status | DI | Via New Control Network |
| WSRTU02_JI510B | Grit Snail 1 Status Running | DI | Via New Control Network |
| WSRTU02_QA510B | Grit Pump 1 Fault | DI | Via New Control Network |
| WSRTU02_ZI510B | Grit Snail 1 Status LOR-Status | DI | Via New Control Network |
| WSRTU02_ZI510C | Grit Teacup 1 Remote | DI | Via New Control Network |
| WSRTU02_ZI510 | Grit System 1 Auto Ready | DI | Via New Control Network |
| WSRTU02_QA510 | Grit System 1 Common Alarm | DI | Via New Control Network |
| WSRTU02_QS510 | Headworks Grit 1 Cycle Init | DO | Via New Control Network |

MCP-520 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | COMMENTS |
|----------------|----------------------------------|------|-------------------------|
| WSRTU02_JI520A | Grit Pump 2 Status Running | DI | Via New Control Network |
| WSRTU02_QA520A | Grit Pump 2 Alarms Starter Fault | DI | Via New Control Network |
| WSRTU02_ZI520A | Grit Pump 2 Status LOR-Status | DI | Via New Control Network |
| WSRTU02_JI520B | Grit Snail 2 Status Running | DI | Via New Control Network |
| WSRTU02_QA520B | Grit Pump 2 Fault | DI | Via New Control Network |
| WSRTU02_ZI520B | Grit Snail 2 Status LOR-Status | DI | Via New Control Network |
| WSRTU02_ZI520C | Grit Teacup 2 Remote | DI | Via New Control Network |
| WSRTU02_ZI520 | Grit System 2 Auto Ready | DI | Via New Control Network |
| WSRTU02_QA520 | Grit System 2 Common Alarm | DI | Via New Control Network |
| WSRTU02_QS520 | Headworks Grit 2 Cycle Init | DO | Via New Control Network |

Existing RTU I/O
(FOR REFERENCE ONLY)

| Existing RTU-1 I/O LIST | | | | | | |
|-------------------------|---|------|--------------------------------------|------|-------|----------|
| PAC TAG | DESCRIPTION | TYPE | Existing RTU (for reference only) | | | COMMENTS |
| | | | RACK | SLOT | POINT | |
| WSRTU01_JI027 | Splitter Box Preaerator Blower Status Running | DI | 1 | 1 | 1 | |
| WSRTU01_ZI027 | Splitter Box Preaerator Blower Command AutoMode | DI | 1 | 1 | 2 | |
| WSRTU01_XA032 | Primary Clarifiers Clarifier 2 Alarms Torque Fault | DI | 1 | 1 | 3 | |
| WSRTU01_JI032 | Primary Clarifiers Clarifier 2 Status Running | DI | 1 | 1 | 4 | |
| WSRTU01_XA031 | Primary Clarifiers Clarifier 1 Alarms Torque Fault | DI | 1 | 1 | 5 | |
| WSRTU01_JI031 | Primary Clarifiers Clarifier 1 Status Running | DI | 1 | 1 | 6 | |
| WSRTU01_JI901 | Primary Sludge & Scum Pump 4 Status Running | DI | 1 | 1 | 7 | |
| WSRTU01_JI902 | Primary Sludge & Scum Pump 3 Status Running | DI | 1 | 1 | 8 | |
| WSRTU01_JI903 | Primary Sludge & Scum Pump 2 Status Running | DI | 1 | 1 | 9 | |
| WSRTU01_JI904 | Primary Sludge & Scum Pump 1 Status Running | DI | 1 | 1 | 10 | |
| WSRTU01_XA033 | Primary Clarifiers Clarifier 3 Alarms Torque Fault | DI | 1 | 1 | 11 | |
| WSRTU01_JI033 | Primary Clarifiers Clarifier 3 Status Running | DI | 1 | 1 | 12 | |
| WSRTU01_JI034 | Primary Clarifiers Clarifier 4 Status Running | DI | 1 | 1 | 13 | |
| WSRTU01_XA034 | Primary Clarifiers Clarifier 4 Alarms Torque Fault | DI | 1 | 1 | 14 | |
| WSRTU01_JI905 | Primary Sludge & Scum Pump 5 Status Running | DI | 1 | 1 | 15 | |
| WSRTU01_JI906 | Primary Sludge & Scum Pump 6 Status Running | DI | 1 | 1 | 16 | |
| WSRTU01_JI907 | Primary Sludge & Scum Pump 7 Status Running | DI | 1 | 1 | 17 | |
| WSRTU01_PAH864A | Disinfection Chlorine Vacuum #1 High | DI | 1 | 1 | 18 | |
| WSRTU01_TAH862 | Disinfection Chlorine Evaporator High Temperature | DI | 1 | 1 | 19 | |
| WSRTU01_PAH864B | Disinfection Chlorine Vacuum #2 High | DI | 1 | 1 | 20 | |
| WSRTU01_PAL864A | Disinfection Chlorine Vacuum #1 Low | DI | 1 | 1 | 21 | |
| WSRTU01_XA867 | Disinfection Chlorine CL2 Leak | DI | 1 | 1 | 22 | |
| WSRTU01_PAL864B | Disinfection Chlorine Vacuum #2 Low | DI | 1 | 1 | 23 | |
| WSRTU01_QA865 | Disinfection Chlorine CL2 Regulator Low | DI | 1 | 1 | 25 | |
| WSRTU01_JI869C | Disinfection Scrubber Fan Running | DI | 1 | 1 | 26 | |
| WSRTU01_JI869B | Disinfection Scrubber Pump Running | DI | 1 | 1 | 27 | |
| WSRTU01_QA855 | Disinfection Sulfonator SO2 Regulator Low | DI | 1 | 1 | 28 | |
| WSRTU01_XA857 | Disinfection Sulfonator SO2 Leak | DI | 1 | 1 | 29 | |
| WSRTU01_PAH854B | Disinfection Sulfonator Sulfonator #1 SO2 Vacuum High | DI | 1 | 1 | 30 | |
| WSRTU01_TAH852 | Disinfection Sulfonator SO2 Evaporator High Temp | DI | 1 | 1 | 31 | |
| WSRTU01_PAH854A | Disinfection Sulfonator Sulfonator #2 SO2 Vacuum High | DI | 1 | 1 | 32 | |
| WSRTU01_PAL854B | Disinfection Sulfonator Sulfonator #1 SO2 Vacuum Low | DI | 1 | 2 | 1 | |
| WSRTU01_PAL854A | Disinfection Sulfonator Sulfonator #2 SO2 Vacuum Low | DI | 1 | 2 | 3 | |
| WSRTU01_JI102 | Sludge Transfer Pump to Truck P1-2 Status Running | DI | 1 | 2 | 4 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|---------------------|--|----|---|---|----|------------------------|
| WSRTU01_JI101 | Sludge Transfer Pump to Truck P1-1 Status Running | DI | 1 | 2 | 5 | |
| WSRTU01_JI091 | Pre-Thickener Rake Status Running | DI | 1 | 2 | 6 | |
| WSRTU01_JI103 | Sludge Transfer Pump to Truck P1-3 Status Running | DI | 1 | 2 | 7 | |
| OFFICE_UP_TRBL | Fire Suppression Office Upstairs Fire Suppression System Trouble | DI | 1 | 2 | 8 | |
| WSRTU01_XA091 | Pre-Thickener Rake Alarms Torque Fault | DI | 1 | 2 | 9 | |
| OFFICE_UP_ALM | Fire Suppression Office Upstairs Fire Suppression System Alarm | DI | 1 | 2 | 10 | |
| OFFICE_DN_TRBL | Fire Suppression Office Downstairs Fire Suppression System Trouble | DI | 1 | 2 | 11 | |
| OFFICE_DN_ALM | Fire Suppression Office Downstairs Fire Suppression System Alarm | DI | 1 | 2 | 12 | |
| WSRTU01_JI869A | Disinfection Scrubber System Ready | DI | 1 | 2 | 13 | |
| WSRTU01_HC027 | Splitter Box Preaerator Blower Status RunCommand | DO | 1 | 3 | 2 | |
| WSRTU01_QS861A | Remote Switch For CL2 Field Controller | DO | 1 | 3 | 3 | Deleted - Field Verify |
| WSRTU01_QS850 | Remote Switch For SO2 Field Controller | DO | 1 | 3 | 4 | Deleted - Field Verify |
| WSRTU01_OPENGATECMD | Unused | DO | 1 | 3 | 5 | Field Verify |
| WSRTU01_FI033 | Primary Sludge & Scum Flow | AI | 1 | 4 | 1 | |
| WSRTU01_ZI861A | Disinfection Chlorine CL2 Flow | AI | 1 | 4 | 2 | |
| WSRTU01_WT868B | Disinfection Sulfonator SO2 Scale 2 Weight | AI | 1 | 4 | 3 | |
| WSRTU01_WT868D | Disinfection Chlorine CL2 Scale 2 Weight | AI | 1 | 4 | 4 | |
| WSRTU01_FI005 | Sludge Transfer Truck Loading Flow | AI | 1 | 4 | 5 | |
| WSRTU01_FI034 | Primary Sludge & Scum Flow 2 | AI | 1 | 4 | 6 | |
| WSRTU01_WT868A | Disinfection Sulfonator SO2 Scale 1 Weight | AI | 1 | 4 | 7 | |
| WSRTU01_WT868C | Disinfection Chlorine CL2 Scale 1 Weight | AI | 1 | 4 | 8 | |
| WSRTU01_ZI850 | Disinfection Sulfonator SO2 Valve Position | AI | 1 | 4 | 9 | |
| WSRTU01_FI081 | Pre-Thickener P95 Flow | AI | 1 | 4 | 10 | |
| WSRTU01_LI040 | Pre-Thickener Sludge Blanket Level | AI | 1 | 4 | 11 | |
| WSRTU01_FI007 | Gas Flows Waste Gas Flow | AI | 1 | 4 | 12 | |
| WSRTU01_FI122 | Gas Flows Influent Gas Flow | AI | 1 | 4 | 13 | |
| WSRTU01_FI082 | Pre-Thickener P96 Flow | AI | 1 | 4 | 15 | |
| WSRTU01_RIC861A | Cl2 Ratio Set | AO | 1 | 5 | 1 | Deleted - Field Verify |
| WSRTU01_RIC850 | SO2 Ratio Set | AO | 1 | 5 | 2 | Deleted - Field Verify |

Existing RTU-2 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | Existing RTU (for reference only) | | | COMMENTS |
|-----------------|---|------|--------------------------------------|------|-------|------------------------|
| | | | RACK | SLOT | POINT | |
| WSRTU02_JI030 | Electrical RTU2 Phase Failure | DI | 1 | 1 | 1 | |
| WSRTU02_LAH011D | Head Works Side #1 Level High | DI | 1 | 1 | 2 | Deleted - Field Verify |
| WSRTU02_JI011 | Headworks Right Side (#1) Climb Screen Status Running | DI | 1 | 1 | 3 | Deleted - Field Verify |
| WSRTU02_JI012 | Headworks Left Side (#2) Climb Screen Status Running | DI | 1 | 1 | 4 | Deleted - Field Verify |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|-------------------|--|----|---|---|----|------------------------|
| WSRTU02_LAH012D | Headworks Right Side Level High | DI | 1 | 1 | 5 | Deleted - Field Verify |
| WSRTU02_QA025 | Influent PS Pump 5 Alarms VFD Fault | DI | 1 | 1 | 6 | |
| WSRTU02_ZI016 | Headworks Conveyer Command AutoMode | DI | 1 | 1 | 7 | Deleted - Field Verify |
| WSRTU02_ZI017 | Preaerator Blower 1 Command AutoMode | DI | 1 | 1 | 8 | Deleted - Field Verify |
| WSRTU02_JI017 | Preaerator Blower 1 Status Running | DI | 1 | 1 | 9 | Deleted - Field Verify |
| WSRTU02_ZI019 | Preaerator Blower 3 Command AutoMode | DI | 1 | 1 | 10 | Deleted - Field Verify |
| WSRTU02_JI019 | Preaerator Blower 3 Status Running | DI | 1 | 1 | 11 | Deleted - Field Verify |
| WSRTU02_XA025A | Influent PS Pump 5 Alarms Seal Fail | DI | 1 | 1 | 12 | |
| WSRTU02_XA025B | | DI | 1 | 1 | 13 | Deleted - Field Verify |
| WSRTU02_JI018 | Preaerator Blower 2 Status Running | DI | 1 | 1 | 14 | Deleted - Field Verify |
| WSRTU02_ZI018 | Preaerator Blower 2 Command AutoMode | DI | 1 | 1 | 15 | Deleted - Field Verify |
| WSRTU02_JI035 | Electrical Generator Running | DI | 1 | 1 | 16 | |
| WSRTU02_XA035 | Electrical Generator General Alarm | DI | 1 | 1 | 17 | |
| WSRTU02_QI021B | Influent PS Low Float - Pump Enable | DI | 1 | 1 | 18 | |
| WSRTU02_MA021 | Influent PS Pump 1 Alarms Seal Fail | DI | 1 | 1 | 19 | |
| WSRTU02_TA021A | Influent PS Pump 1 Alarms High Motor Temp | DI | 1 | 1 | 20 | |
| WSRTU02_ZI021A_IN | Influent PS Pump 1 Status VFD in AUTO | DI | 1 | 1 | 21 | |
| WSRTU02_JI021 | Influent PS Pump 1 Status VFD Running | DI | 1 | 1 | 22 | |
| WSRTU02_QA021 | Influent PS Pump 1 Alarms VFD Fault | DI | 1 | 1 | 23 | |
| WSRTU02_ZI021B | Influent PS Pump 1 Status Field-Remote | DI | 1 | 1 | 24 | |
| WSRTU02_ZI021C | Influent PS Pump 1 Status VFD Mode Feedback | DI | 1 | 1 | 25 | |
| WSRTU02_ZI021D | Influent PS Pump 1 Status Bypass Mode Feedback | DI | 1 | 1 | 26 | |
| WSRTU02_LA021A_IN | Influent PS Wet Well Level Transmitter Failure | DI | 1 | 1 | 27 | |
| WSRTU02_MA022 | Influent PS Pump 2 Alarms Seal Fail | DI | 1 | 1 | 28 | |
| WSRTU02_TA022A_IN | Influent PS Pump 2 Alarms High Temp | DI | 1 | 1 | 29 | |
| WSRTU02_ZI022A_IN | Influent PS Pump 2 Status VFD in AUTO | DI | 1 | 1 | 30 | |
| WSRTU02_JI022 | Influent PS Pump 2 Status VFD Running | DI | 1 | 1 | 31 | |
| WSRTU02_QA022 | Influent PS Pump 2 Alarms VFD Fault | DI | 1 | 1 | 32 | |
| WSRTU02_ZI022B | Influent PS Pump 2 Status Field-Remote | DI | 1 | 2 | 1 | |
| WSRTU02_ZI022C | Influent PS Pump 2 Status VFD Mode Feedback | DI | 1 | 2 | 2 | |
| WSRTU02_ZI022D | Influent PS Pump 2 Status Bypass Mode Feedback | DI | 1 | 2 | 3 | |
| WSRTU02_MA023 | Influent PS Pump 3 Status High Moisture | DI | 1 | 2 | 4 | |
| WSRTU02_TA023A_IN | Influent PS Pump 3 Status High Temp | DI | 1 | 2 | 5 | |
| WSRTU02_ZI023A_IN | Influent PS Pump 3 Status VFD in AUTO | DI | 1 | 2 | 6 | |
| WSRTU02_JI023 | Influent PS Pump 3 Status VFD Running | DI | 1 | 2 | 7 | |
| WSRTU02_QA023 | Influent PS Pump 3 Alarms VFD Fault | DI | 1 | 2 | 8 | |
| WSRTU02_ZI023B | Influent PS Pump 3 Status Field-Remote | DI | 1 | 2 | 9 | |
| WSRTU02_ZI023C | Influent PS Pump 3 Status VFD Mode Feedback | DI | 1 | 2 | 10 | |
| WSRTU02_ZI023D | Influent PS Pump 3 Status Bypass Mode Feedback | DI | 1 | 2 | 11 | |
| WSRTU02_JI025OLD | | DI | 1 | 2 | 12 | Deleted - Field Verify |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------------|---|----|---|---|----|------------------------|
| WSRTU02_ZI025OLD | | DI | 1 | 2 | 13 | Deleted - Field Verify |
| WSRTU02_LAH021A | Influent PS Pumps Dry Well High Level | DI | 1 | 2 | 14 | |
| WSRTU02_JI095 | Pre-Thickener Pumps P95 Status Running | DI | 1 | 2 | 16 | |
| WSRTU02_ZI095 | Pre-Thickener Pumps P95 Status Field-Remote | DI | 1 | 2 | 17 | |
| WSRTU02_JI096 | Pre-Thickener Pumps P96 Status Running | DI | 1 | 2 | 18 | |
| WSRTU02_ZI096 | Pre-Thickener Pumps P96 In Auto | DI | 1 | 2 | 19 | |
| WSRTU02_JI092 | Post Thickener Rake Status Running | DI | 1 | 2 | 20 | |
| WSRTU02_JI122 | Digesters Heat Exchangers Hot Water Pump #2 Running | DI | 1 | 2 | 21 | |
| WSRTU02_JI121 | Digesters Heat Exchangers Hot Water Pump #1 Running | DI | 1 | 2 | 22 | |
| WSRTU02_LLI050 | Digesters Heat Exchangers Hot Water Make Up Tank Low Level | DI | 1 | 2 | 23 | |
| WSRTU02_JI047 | Digesters Sludge Recirc P112 Status Running | DI | 1 | 2 | 24 | |
| WSRTU02_ZI047 | Digesters Sludge Recirc P112 Status MCC-Remote | DI | 1 | 2 | 25 | |
| WSRTU02_JI048 | Digesters Sludge Recirc P113 Status Running | DI | 1 | 2 | 26 | |
| WSRTU02_ZI048 | Digesters Sludge Recirc P113 Status MCC-Remote | DI | 1 | 2 | 27 | |
| WSRTU02_JI111 | Digesters Mixing Gas Compressor #1 Running | DI | 1 | 2 | 28 | |
| WSRTU02_JI112 | Digesters Mixing Gas Compressor #2 Running | DI | 1 | 2 | 29 | |
| WSRTU02_JI113 | Digesters Mixing Gas Compressor #3 Running | DI | 1 | 2 | 30 | |
| WSRTU02_JI114 | Digesters Mixing Gas Compressor #4 Running | DI | 1 | 2 | 31 | |
| WSRTU02_ZI092 | Post-Thickener Rake Torque Fault | DI | 1 | 2 | 32 | |
| WSRTU02_JI071 | Final Clarifier Rakes Rake 1 Status Running | DI | 1 | 3 | 1 | |
| WSRTU02_XA071 | Final Clarifier Rakes Rake 1 Alarms Starter Fault | DI | 1 | 3 | 2 | |
| WSRTU02_JI072 | Final Clarifier Rakes Rake 2 Final Clarifier Rake #2 Running | DI | 1 | 3 | 3 | |
| WSRTU02_XA072 | Final Clarifier Rakes Rake 2 Alarms Starter Fault | DI | 1 | 3 | 4 | |
| WSRTU02_JI046 | Digesters Sludge Recirc P111 Status Running | DI | 1 | 3 | 5 | |
| WSRTU02_ZI046 | Digesters Sludge Recirc P111 Status MCC-Remote | DI | 1 | 3 | 6 | |
| WSRTU02_MA024 | Influent PS Pump 4 Alarms Seal Fail | DI | 1 | 3 | 7 | |
| WSRTU02_TA024A_IN | Influent PS Pump 4 Alarms High Temp | DI | 1 | 3 | 8 | |
| WSRTU02_ZI024A | Influent PS Pump 4 Status VFD in AUTO | DI | 1 | 3 | 9 | |
| WSRTU02_JI024 | Influent PS Pump 4 Status Running | DI | 1 | 3 | 10 | |
| WSRTU02_OA024 | Influent PS Pump 4 Alarms VFD Fault | DI | 1 | 3 | 11 | |
| WSRTU02_JI025 | Influent PS Pump 5 Status Running | DI | 1 | 3 | 12 | |
| WSRTU02_ZI025A | Influent PS Pump 5 Status VFD in AUTO | DI | 1 | 3 | 13 | |
| WSRTU02_ZI025B | Influent PS Pump 5 Status Field-Remote | DI | 1 | 3 | 14 | |
| WSRTU02_JI115 | Digesters Heat Exchangers Gas Boiler Running | DI | 1 | 3 | 15 | |
| RTU2_TRBL | Fire Suppression Generator Building Fire Suppression System Trouble | DI | 1 | 3 | 17 | |
| RTU2_ALM | Fire Suppression Generator Building Fire Suppression System Alarm | DI | 1 | 3 | 18 | |
| WSRTU2_PS1_OK | Electrical RTU2 Power Supply 1 Fault | DI | 1 | 3 | 21 | |
| WSRTU2_PS2_OK | Electrical RTU2 Power Supply 2 Fault | DI | 1 | 3 | 22 | |
| WSRTU02_FQI100_PULSE | Influent Flow Totalizer Pulse | DI | 1 | 3 | 23 | |
| WSRTU02_FQI110_PULSE | Band Screen Channel Flow Totalizer Pulse | DI | 1 | 3 | 24 | Deleted - Field Verify |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|-----------------------|--|----|---|---|----|------------------------|
| WSRTU02_LSH110 | Band Screen Channel High Level Float | DI | 1 | 3 | 25 | Deleted - Field Verify |
| WSRTU02_SCRN110_ON | Band Screen Running | DI | 1 | 3 | 26 | Deleted - Field Verify |
| WSRTU02_SCRN110_FAIL | Band Screen Fail | DI | 1 | 3 | 27 | Deleted - Field Verify |
| WSRTU02_SCRN110_ESTOP | Band Screen Estopped | DI | 1 | 3 | 28 | Deleted - Field Verify |
| WSRTU02_SCRN120_ON | Band Screen Press Running | DI | 1 | 3 | 29 | Deleted - Field Verify |
| WSRTU02_SCRN120_FAIL | Band Screen Press Fail | DI | 1 | 3 | 30 | Deleted - Field Verify |
| WSRTU02_P130_ON | Band Screen Wash Water Pump Running | DI | 1 | 3 | 31 | Deleted - Field Verify |
| WSRTU02_P130_FAIL | Band Screen Wash Water Pump Fail | DI | 1 | 3 | 32 | Deleted - Field Verify |
| WSRTU02_HS110 | Grit Remover Status RunCommand | DO | 1 | 4 | 1 | |
| WSRTU02_HS200 | Headworks Screen 1 Start Cycle Output | DO | 1 | 4 | 2 | |
| WSRTU02_HS250 | Headworks Screen 2 Start Cycle Output | DO | 1 | 4 | 3 | |
| WSRTU02_HS017 | Preaerator Blower 1 Status RunCommand | DO | 1 | 4 | 4 | Deleted - Field Verify |
| WSRTU02_HS019 | Preaerator Blower 3 Status RunCommand | DO | 1 | 4 | 5 | Deleted - Field Verify |
| WSRTU02_HS018 | Preaerator Blower 2 Status RunCommand | DO | 1 | 4 | 7 | Deleted - Field Verify |
| WSRTU02_QS021A | Influent PS Pump 1 Status RunCommand | DO | 1 | 4 | 8 | |
| WSRTU02_HS021B | Influent Pump #1 VFD Remote Drive Mode | DO | 1 | 4 | 9 | |
| WSRTU02_HS021C | Influent Pump #1 VFD Remote Stop | DO | 1 | 4 | 10 | |
| WSRTU02_HS021D | Influent Pump #1 VFD Remote Bypass Mode | DO | 1 | 4 | 11 | |
| WSRTU02_QS022A | Influent PS Pump 2 Status RunCommand | DO | 1 | 4 | 12 | |
| WSRTU02_HS022B | Influent Pump #2 VFD Remote Drive Mode | DO | 1 | 4 | 13 | |
| WSRTU02_HS022C | Influent Pump #2 VFD Remote Stop | DO | 1 | 4 | 14 | |
| WSRTU02_HS022D | Influent Pump #2 VFD Remote Bypass Mode | DO | 1 | 4 | 15 | |
| WSRTU02_QS023A | Influent PS Pump 3 Status RunCommand | DO | 1 | 4 | 16 | |
| WSRTU02_HS023B | Influent Pump #3 VFD Remote Drive Mode | DO | 1 | 4 | 17 | |
| WSRTU02_HS023C | Influent Pump #3 VFD Remote Stop | DO | 1 | 4 | 18 | |
| WSRTU02_HS023D | Influent Pump #3 VFD Remote Bypass Mode | DO | 1 | 4 | 19 | |
| WSRTU02_HS025A | Influent Pump #5 Run Relay | DO | 1 | 4 | 20 | |
| WSRTU02_HC095 | Pre-Thickener Pumps P95 Status RunCommand | DO | 1 | 4 | 21 | |
| WSRTU02_HC096 | Pre-Thickener Pumps P96 Status RunCommand | DO | 1 | 4 | 22 | |
| WSRTU02_HS046 | Digesters Sludge Recirc P111 Status RunCommand | DO | 1 | 4 | 23 | |
| WSRTU02_HS047 | Digesters Sludge Recirc P112 Status RunCommand | DO | 1 | 4 | 24 | |
| WSRTU02_HS048 | Digesters Sludge Recirc P113 Status RunCommand | DO | 1 | 4 | 25 | |
| WSRTU02_QS024A | Influent PS Pump 4 Status RunCommand | DO | 1 | 4 | 28 | |
| WSRTU02_QS510 | Headworks Grit 1 Cycle Init | DO | 1 | 4 | 29 | |
| WSRTU02_QS520 | Headworks Grit 2 Cycle Init | DO | 1 | 4 | 30 | |
| WSRTU02_QS025 | Influent PS Pump 5 Status RunCommand | DO | 1 | 4 | 31 | |
| WSRTU02_LI011A | Headworks Differential Level Left Side | AI | 1 | 5 | 1 | Deleted - Field Verify |
| WSRTU02_LI012 | Headworks Differential Level Right Side | AI | 1 | 5 | 2 | Deleted - Field Verify |
| WSRTU02_LI011B | Headworks Level A | AI | 1 | 5 | 3 | Deleted - Field Verify |
| WSRTU02_LI012B | Headworks Level B | AI | 1 | 5 | 4 | Deleted - Field Verify |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------------|---|----|---|---|----|------------------------|
| WSRTU02_XI035_RAW | Influent Generator Amps | AI | 1 | 5 | 5 | |
| WSRTU02_XI021 | Influent PS Pump 1 Motor Load | AI | 1 | 5 | 6 | |
| WSRTU02_SIC021 | Influent PS Pump 1 Speed Feedback | AI | 1 | 5 | 7 | |
| WSRTU02_LIC021 | Influent PS Wet Well Level | AI | 1 | 5 | 8 | |
| WSRTU02_SIC022 | Influent PS Pump 2 Speed Feedback | AI | 1 | 5 | 9 | |
| WSRTU02_XI022 | Influent PS Pump 2 Motor Load | AI | 1 | 5 | 10 | |
| WSRTU02_SIC023 | Influent PS Pump 3 Speed Feedback | AI | 1 | 5 | 11 | |
| WSRTU02_XI023 | Influent PS Pump 3 Motor Load | AI | 1 | 5 | 12 | |
| INFLUENT_FLOW | WS Influent Flow | AI | 1 | 5 | 13 | Deleted - Field Verify |
| WSRTU02_LT3000 | | AI | 1 | 5 | 14 | Deleted - Field Verify |
| WSRTU02_LT4000 | | AI | 1 | 5 | 15 | Deleted - Field Verify |
| WSRTU02_TI042 | Digesters Digester 1 Sludge Temperature | AI | 1 | 6 | 1 | |
| WSRTU02_TI043 | Digesters Digester 2 Sludge Temperature | AI | 1 | 6 | 2 | |
| WSRTU02_TI045 | Digesters Digester 2 Temperature | AI | 1 | 6 | 3 | |
| WSRTU02_TI044 | Digesters Digester 1 Temperature | AI | 1 | 6 | 4 | |
| WSRTU02_SCC021 | Influent PS Pump 1 Speed Command | AO | 1 | 7 | 1 | |
| WSRTU02_SCC022 | Influent PS Pump 2 Speed Command | AO | 1 | 7 | 2 | |
| WSRTU02_SCC023 | Influent PS Pump 3 Speed Command | AO | 1 | 7 | 3 | |
| WSRTU02_SCC024 | Influent PS Pump 4 Speed Manual Cmd | AO | 1 | 7 | 4 | |
| WSRTU02_SCC025 | Influent PS Pump 5 Speed Manual Cmd | AO | 1 | 7 | 5 | |
| WSRTU02_SIC024 | Influent PS Pump 4 Speed Feedback | AI | 1 | 8 | 1 | |
| WSRTU02_XI024 | Influent PS Pump 4 Motor Load | AI | 1 | 8 | 2 | |
| WSRTU02_LI110A | Band Screen Upstream Level | AI | 1 | 8 | 3 | Deleted - Field Verify |
| WSRTU02_LI110B | Band Screen Downstream Level | AI | 1 | 8 | 4 | Deleted - Field Verify |
| WSRTU02_LI201A | Headworks Screen 1 Upstream Level | AI | 1 | 8 | 5 | |
| WSRTU02_LI201B | Headworks Screen 1 Downstream Level | AI | 1 | 8 | 6 | |
| WSRTU02_LI251A | Headworks Screen 2 Upstream Level | AI | 1 | 8 | 7 | |
| WSRTU02_LI251B | Headworks Screen 2 Downstream Level | AI | 1 | 8 | 8 | |
| WSRTU02_FIT100 | Influent PS Sewage Flow | AI | 1 | 8 | 9 | |
| WSRTU02_FIT200 | Headworks Discharge Flow | AI | 1 | 8 | 10 | |
| WSRTU02_FIT110 | Band Screen Channel Flow | AI | 1 | 8 | 11 | Deleted - Field Verify |
| WSRTU02_SIC025 | Influent PS Pump 5 Speed Feedback | AI | 1 | 8 | 13 | |
| WSRTU02_XI025 | Electrical MCC1 Amps | AI | 1 | 8 | 14 | |
| WSRTU02_SCRN200A_REM | Headworks Screen 1 Status Field-Remote | DI | 2 | 1 | 1 | |
| WSRTU02_SCRN200A_ON | Headworks Screen 1 Status Running | DI | 2 | 1 | 2 | |
| WSRTU02_SCRN200A_ALM | Headworks Screen 1 Alarms Common Alarm | DI | 2 | 1 | 3 | |
| WSRTU02_LSH200 | Headworks Screen 1 Alarms Alarm Word Channel Level High | DI | 2 | 1 | 4 | |
| WSRTU02_SCRN200B_REM | Headworks Screen 1 Press Status LOR-Status | DI | 2 | 1 | 5 | |
| WSRTU02_SCRN200B_ON | Headworks Screen 1 Press Status Running | DI | 2 | 1 | 6 | |
| WSRTU02_SCRN200_ALM | Headworks Screen 1 Alarms Alarm | DI | 2 | 1 | 7 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------------|---|----|---|---|----|--|
| WSRTU02_SCRN250A_REM | Headworks Screen 2 Status Field-Remote | DI | 2 | 1 | 8 | |
| WSRTU02_SCRN250A_ON | Headworks Screen 2 Status Running | DI | 2 | 1 | 9 | |
| WSRTU02_SCRN250A_ALM | Headworks Screen 1 Press Alarms Common Alarm | DI | 2 | 1 | 10 | |
| WSRTU02_LSH250 | Headworks Screen 2 Alarms Alarm Word Channel Level High | DI | 2 | 1 | 11 | |
| WSRTU02_SCRN250B_REM | Headworks Screen 2 Press Status LOR-Status | DI | 2 | 1 | 12 | |
| WSRTU02_SCRN250B_ON | Headworks Screen 2 Press Status Running | DI | 2 | 1 | 13 | |
| WSRTU02_SCRN250B_ALM | Headworks Screen 2 Press Alarms Common Alarm | DI | 2 | 1 | 14 | |
| WSRTU02_JI510A | Grit Pump 1 Status Running | DI | 2 | 1 | 15 | |
| WSRTU02_QA510A | Grit Pump 1 Alarms Starter Fault | DI | 2 | 1 | 16 | |
| WSRTU02_ZI510A | Grit Pump 1 Status LOR-Status | DI | 2 | 1 | 17 | |
| WSRTU02_JI510B | Grit Snail 1 Status Running | DI | 2 | 1 | 18 | |
| WSRTU02_QA510B | Grit Pump 1 Fault | DI | 2 | 1 | 19 | |
| WSRTU02_ZI510B | Grit Snail 1 Status LOR-Status | DI | 2 | 1 | 20 | |
| WSRTU02_ZI510C | Grit Teacup 1 Remote | DI | 2 | 1 | 21 | |
| WSRTU02_ZI510 | Grit System 1 Auto Ready | DI | 2 | 1 | 22 | |
| WSRTU02_QA510 | Grit System 1 Common Alarm | DI | 2 | 1 | 23 | |
| WSRTU02_JI520A | Grit Pump 2 Status Running | DI | 2 | 1 | 24 | |
| WSRTU02_QA520A | Grit Pump 2 Alarms Starter Fault | DI | 2 | 1 | 25 | |
| WSRTU02_ZI520A | Grit Pump 2 Status LOR-Status | DI | 2 | 1 | 26 | |
| WSRTU02_JI520B | Grit Snail 2 Status Running | DI | 2 | 1 | 27 | |
| WSRTU02_QA520B | Grit Pump 2 Fault | DI | 2 | 1 | 28 | |
| WSRTU02_ZI520B | Grit Snail 2 Status LOR-Status | DI | 2 | 1 | 29 | |
| WSRTU02_ZI520C | Grit Teacup 2 Remote | DI | 2 | 1 | 30 | |
| WSRTU02_ZI520 | Grit System 2 Auto Ready | DI | 2 | 1 | 31 | |
| WSRTU02_QA520 | Grit System 2 Common Alarm | DI | 2 | 1 | 32 | |

Existing RTU-3 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | Existing RTU (for reference only) | | | COMMENTS |
|---------------|---|------|--------------------------------------|------|-------|----------|
| | | | RACK | SLOT | POINT | |
| WSRTU03_JI043 | Intermediate Clarifiers Rake 3 Status Running | DI | 1 | 1 | 1 | |
| WSRTU03_XA043 | Intermediate Clarifiers Rake 3 Alarms Starter Fault | DI | 1 | 1 | 2 | |
| WSRTU03_JI044 | Intermediate Clarifiers Rake 4 Status Running | DI | 1 | 1 | 3 | |
| WSRTU03_XA044 | Intermediate Clarifiers Rake 4 Alarms Starter Fault | DI | 1 | 1 | 4 | |
| WSRTU03_ZI037 | Recycle Pump 1 Status Field-Remote | DI | 1 | 1 | 5 | |
| WSRTU03_JI037 | Recycle Pump 1 Status Running | DI | 1 | 1 | 6 | |
| WSRTU03_XA037 | Recycle Pump 1 Alarms VFD Fault | DI | 1 | 1 | 7 | |
| WSRTU03_ZI038 | Recycle Pump 2 Status Field-Remote | DI | 1 | 1 | 8 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | |
|-------------------|--|----|---|---|----|
| WSRTU03_JI038 | Recycle Pump 2 Status Running | DI | 1 | 1 | 9 |
| WSRTU03_XA038 | Recycle Pump 2 Alarms VFD Fault | DI | 1 | 1 | 10 |
| WSRTU03_ZI039 | Recycle Pump 3 Status Field-Remote | DI | 1 | 1 | 11 |
| WSRTU03_JI039 | Recycle Pump 3 Status Running | DI | 1 | 1 | 12 |
| WSRTU03_XA039 | Recycle Pump 3 Alarms VFD Fault | DI | 1 | 1 | 13 |
| WSRTU03_ZI051A_IN | Secondary LS Pump 3 Status VFD in AUTO | DI | 1 | 1 | 14 |
| WSRTU03_JI051 | Secondary LS Pump 3 Status VFD Running | DI | 1 | 1 | 15 |
| WSRTU03_XA051 | Secondary LS Pump 3 Alarms VFD Fault | DI | 1 | 1 | 16 |
| WSRTU03_ZI051B | Secondary Pump #3 VFD In Remote | DI | 1 | 1 | 17 |
| WSRTU03_ZI051C | Secondary Pump #3 VFD Drive Mode | DI | 1 | 1 | 18 |
| WSRTU03_ZI051D | Secondary LS Pump 3 Status Bypass Running | DI | 1 | 1 | 19 |
| WSRTU03_XA051B | Secondary LS Pumps Wet Well Transmitter Fail | DI | 1 | 1 | 20 |
| WSRTU03_ZI052A_IN | Secondary LS Pump 2 Status VFD in AUTO | DI | 1 | 1 | 21 |
| WSRTU03_JI052 | Secondary LS Pump 4 Status VFD Running | DI | 1 | 1 | 22 |
| WSRTU03_XA052 | Secondary LS Pump 4 Alarms VFD Fault | DI | 1 | 1 | 23 |
| WSRTU03_ZI052B | Secondary LS Pump #4 VFD In Remote | DI | 1 | 1 | 24 |
| WSRTU03_ZI052C | Secondary LS Pump #4 VFD Drive Mode | DI | 1 | 1 | 25 |
| WSRTU03_ZI052D | Secondary LS Pump 4 Status Bypass Running | DI | 1 | 1 | 26 |
| WSRTU03_ZI053A_IN | Secondary LS Pump 3 Status VFD in AUTO | DI | 1 | 1 | 27 |
| WSRTU03_JI053 | Secondary LS Pump 1 Status Running | DI | 1 | 1 | 28 |
| WSRTU03_XA053 | Secondary LS Pump 1 Alarms VFD Fault | DI | 1 | 1 | 29 |
| WSRTU03_ZI054A_IN | Secondary LS Pump 4 Status VFD in AUTO | DI | 1 | 1 | 30 |
| WSRTU03_JI054 | Secondary LS Pump 2 Status Running | DI | 1 | 1 | 31 |
| WSRTU03_XA054 | Secondary LS Pump 2 Alarms VFD Fault | DI | 1 | 1 | 32 |
| WSRTU03_JI061 | Nitrification Recirc. Pump 1 Status Running | DI | 1 | 2 | 1 |
| WSRTU03_ZI061 | Nitrification Recirc. Pump 1 Command AutoMode | DI | 1 | 2 | 2 |
| WSRTU03_JI062 | Nitrification Recirc. Pump 2 Status Running | DI | 1 | 2 | 3 |
| WSRTU03_ZI062 | Nitrification Recirc. Pump 2 Command AutoMode | DI | 1 | 2 | 4 |
| WSRTU03_JI063 | Nitrification Recirc. Pump 3 Status Running | DI | 1 | 2 | 5 |
| WSRTU03_ZI063 | Nitrification Recirc. Pump 3 Command AutoMode | DI | 1 | 2 | 6 |
| WSRTU03_JI064 | Nitrification Recirc. Pump 4 Status Running | DI | 1 | 2 | 7 |
| WSRTU03_ZI064 | Nitrification Recirc. Pump 4 Command AutoMode | DI | 1 | 2 | 8 |
| RTU3_TRBL | Fire Suppression RTU3 Building Fire Suppression System Trouble | DI | 1 | 2 | 9 |
| RTU3_ALM | Fire Suppression RTU3 Building Fire Suppression System Alarm | DI | 1 | 2 | 10 |
| WSRTU03_ZI041A | Secondary Clarifier #1 Actuator In Auto | DI | 1 | 2 | 11 |
| WSRTU03_ZI036A | Secondary Clarifier #2 Actuator In Auto | DI | 1 | 2 | 12 |
| WSRTU03_ZI011A | Final Clarifier Valves Discharge Valve 1 Status Field-Remote | DI | 1 | 2 | 13 |
| WSRTU03_ZI012A | Final Clarifier Valves Discharge Valve 2 Status Field-Remote | DI | 1 | 2 | 14 |
| WSRTU03_JI081 | Post-Aeration Mixer 1 Status Running | DI | 1 | 2 | 15 |
| WSRTU03_JI082 | Post-Aeration Mixer 2 Status Running | DI | 1 | 2 | 16 |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------|---|----|---|---|----|--|
| WSRTU03_JI083 | Reuse Water Pump #1 Running | DI | 1 | 2 | 17 | |
| WSRTU03_ZI083 | Reuse Water Pump #1 In Auto | DI | 1 | 2 | 18 | |
| WSRTU03_JI084 | Reuse Water Pump 2 Status Running | DI | 1 | 2 | 19 | |
| WSRTU03_ZI084 | Reuse Water Pump 2 Command AutoMode | DI | 1 | 2 | 20 | |
| WSRTU03_QI051B | Secondary LS Low Float | DI | 1 | 2 | 21 | |
| WSRTU03_ZI101 | Trickle Filters Discharge Valve 1 Status Field-Remote | DI | 1 | 2 | 23 | |
| WSRTU03_ZI102 | Trickle Filters Discharge Valve 2 Status Field-Remote | DI | 1 | 2 | 25 | |
| WSRTU03_HC037A | Recycle Pump 1 Status RunCommand | DO | 1 | 3 | 1 | |
| WSRTU03_HC037B | Recycle Pump #1 Stop | DO | 1 | 3 | 2 | |
| WSRTU03_HC038A | Recycle Pump 2 Status RunCommand | DO | 1 | 3 | 3 | |
| WSRTU03_HC038B | Recycle Pump #2 Stop | DO | 1 | 3 | 4 | |
| WSRTU03_HC039A | Recycle Pump 3 Status RunCommand | DO | 1 | 3 | 5 | |
| WSRTU03_HC039B | Recycle Pump #3 Stop | DO | 1 | 3 | 6 | |
| WSRTU03_QS051A | Secondary LS Pump 3 Status RunCommand | DO | 1 | 3 | 7 | |
| WSRTU03_JY051B | Secondary Pump #3 VFD Remote Drive Mode | DO | 1 | 3 | 8 | |
| WSRTU03_JY051C | Secondary Pump #3 VFD Remote Stop | DO | 1 | 3 | 9 | |
| WSRTU03_JY051D | Secondary Pump #3 VFD Remote Bypass Mode | DO | 1 | 3 | 10 | |
| WSRTU03_QS052A | Secondary LS Pump 4 Status RunCommand | DO | 1 | 3 | 11 | |
| WSRTU03_JY052B | Secondary Pump #4 VFD Remote Drive Mode | DO | 1 | 3 | 12 | |
| WSRTU03_JY052C | Secondary Pump #4 VFD Remote Stop | DO | 1 | 3 | 13 | |
| WSRTU03_JY052D | Secondary Pump #4 VFD Remote Bypass Mode | DO | 1 | 3 | 14 | |
| WSRTU03_QS053A | Secondary LS Pump 1 Status RunCommand | DO | 1 | 3 | 15 | |
| WSRTU03_QS054A | Secondary LS Pump 2 Status RunCommand | DO | 1 | 3 | 16 | |
| WSRTU03_HS061 | Nitrification Recirc. Pump 1 Status RunCommand | DO | 1 | 3 | 17 | |
| WSRTU03_HS062 | Nitrification Recirc. Pump 2 SS | DO | 1 | 3 | 18 | |
| WSRTU03_HS063 | Nitrification Recirc. Pump 3 Status RunCommand | DO | 1 | 3 | 19 | |
| WSRTU03_HS064 | Nitrification Recirc. Pump 4 Status RunCommand | DO | 1 | 3 | 20 | |
| WSRTU03_HS083 | Reuse Water Pump 1 SS | DO | 1 | 3 | 21 | |
| WSRTU03_HS084 | Reuse Water Pump 2 SS | DO | 1 | 3 | 22 | |
| WSRTU03_ZI036 | Intermediate Clarifiers Discharge Valve 2 Position Feedback | AI | 1 | 4 | 2 | |
| WSRTU03_FI035 | Recycle Flow | AI | 1 | 4 | 3 | |
| WSRTU03_SIC037 | Recycle Pump 1 Speed Feedback | AI | 1 | 4 | 4 | |
| WSRTU03_SIC038 | Recycle Pump 2 Speed Feedback | AI | 1 | 4 | 5 | |
| WSRTU03_SIC039 | Recycle Pump 3 Speed Feedback | AI | 1 | 4 | 6 | |
| WSRTU03_SIC051 | Secondary LS Pump 3 Speed Feedback | AI | 1 | 4 | 7 | |
| WSRTU03_LIC051 | Secondary LS Pumping Station Level | AI | 1 | 4 | 8 | |
| WSRTU03_SIC052 | Secondary LS Pump 4 Speed Feedback | AI | 1 | 4 | 9 | |
| WSRTU03_SIC053 | Secondary LS Pump 1 Speed Feedback | AI | 1 | 4 | 10 | |
| WSRTU03_SIC054 | Secondary LS Pump 2 Speed Feedback | AI | 1 | 4 | 11 | |
| WSRTU03_FI071 | Disinfection Flow CCC Flow | AI | 1 | 4 | 14 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------|--|----|---|---|----|--|
| WSRTU03_XI851 | Post-Aeration CL2 Analyzer | AI | 1 | 4 | 15 | |
| WSRTU03_XI850 | Post-Aeration SO2 Analyzer | AI | 1 | 4 | 16 | |
| WSRTU03_ZI041 | Intermediate Clarifiers Discharge Valve 1 Position Feedback | AI | 1 | 5 | 1 | |
| WSRTU03_ZT101 | Trickle Filters Discharge Valve 1 Position Feedback | AI | 1 | 5 | 5 | |
| WSRTU03_ZT102 | Trickle Filters Discharge Valve 2 Position Feedback | AI | 1 | 5 | 6 | |
| WSRTU03_ZI011B | Final Clarifier Valves Discharge Valve 1 Position Feedback | AI | 1 | 5 | 7 | |
| WSRTU03_ZI012B | Final Clarifier Valves Discharge Valve 2 Position Feedback | AI | 1 | 5 | 8 | |
| WSRTU03_HIC041 | Intermediate Clarifiers Discharge Valve 1 Commanded Position | AO | 1 | 6 | 1 | |
| WSRTU03_HIC036 | Intermediate Clarifiers Discharge Valve 2 Commanded Position | AO | 1 | 6 | 2 | |
| WSRTU03_SCC037 | Recycle Pump #1 VFD Speed SP | AO | 1 | 6 | 3 | |
| WSRTU03_SCC038 | Recycle Pump #2 VFD Speed SP | AO | 1 | 6 | 4 | |
| WSRTU03_SCC039 | Recycle Pump #3 VFD Speed SP | AO | 1 | 6 | 5 | |
| WSRTU03_SCC051 | Secondary Pump #3 VFD Speed SP | AO | 1 | 6 | 6 | |
| WSRTU03_SCC052 | Secondary Pump #4 VFD Speed SP | AO | 1 | 6 | 7 | |
| WSRTU03_SCC053 | Secondary Pump #1 VFD Speed SP | AO | 1 | 6 | 8 | |
| WSRTU03_SCC054 | Secondary Pump #2 VFD Speed SP | AO | 1 | 7 | 1 | |
| WSRTU03_HIC012 | Final Clarifier Valves Discharge Valve 2 Commanded Position | AO | 1 | 7 | 3 | |
| WSRTU03_HIC101 | Trickle Filters Discharge Valve 1 Commanded Position | AO | 1 | 7 | 4 | |
| WSRTU03_HIC102 | Trickle Filters Discharge Valve 2 Commanded Position | AO | 1 | 7 | 5 | |
| WSRTU03_HIC011 | Final Clarifier Valves Discharge Valve 1 Commanded Position | AO | 1 | 7 | 6 | |

Existing RTU-5 I/O LIST

| PAC TAG | DESCRIPTION | TYPE | Existing RTU (for reference only) | | | COMMENTS |
|------------------------|-------------------------------------|------|--------------------------------------|------|-------|----------|
| | | | RACK | SLOT | POINT | |
| WSRTU05_GENRUNNING | Effluent Area Generator Running | DI | 1 | 1 | 1 | |
| WSRTU05_GENALARM | Effluent Area Generator Alarm | DI | 1 | 1 | 2 | |
| WSRTU05_ATSGEN | Effluent Area Generator ATS on GEN | DI | 1 | 1 | 3 | |
| WSRTU05_ATSUTILITY | Effluent Area Generator ATS on UTIL | DI | 1 | 1 | 4 | |
| WSRTU05_ATSAUTO | Effluent Area Generator ATS AUTO | DI | 1 | 1 | 5 | |
| WSRTU05_ATSALARM | Effluent Area Generator ATS Alarm | DI | 1 | 1 | 6 | |
| WSRTU05_FIRESUPSYS | Effluent Area Fire Supp Active | DI | 1 | 1 | 7 | |
| WSRTU05_WETWELLHIGHLVL | Effluent Wet Well High Level Float | DI | 1 | 1 | 8 | |
| WSRTU05_RESET | Reset Pushbutton | DI | 1 | 1 | 9 | |
| WSRTU05_FAULTDRIVE1 | Effluent Pump 1 VFD Fault | DI | 1 | 1 | 10 | |
| WSRTU05_FAULTDRIVE2 | Effluent Pump 2 VFD Fault | DI | 1 | 1 | 11 | |
| WSRTU05_FAULTDRIVE3 | Effluent Pump 3 VFD Fault | DI | 1 | 1 | 12 | |
| WSRTU05_FAULTDRIVE4 | Effluent Pump 4 VFD Fault | DI | 1 | 1 | 13 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------------------|--|----|---|---|----|----------------------|
| WSRTU05_FAULTDRIVE5 | Effluent Pump 5 VFD Fault | DI | 1 | 1 | 14 | |
| WSRTU05_CHKVLV1 | Effluent Pump 1 Check Valve Closed | DI | 1 | 1 | 15 | |
| WSRTU05_CHKVLV2 | Effluent Pump 2 Check Valve Closed | DI | 1 | 1 | 16 | |
| WSRTU05_CHKVLV3 | Effluent Pump 3 Check Valve Closed | DI | 1 | 1 | 17 | |
| WSRTU05_CHKVLV4 | Effluent Pump 4 Check Valve Closed | DI | 1 | 1 | 18 | |
| WSRTU05_CHKVLV5 | Effluent Pump 5 Check Valve Closed | DI | 1 | 1 | 19 | |
| WSRTU05_VFDRUN1 | Effluent Pump 1 VFD Running | DI | 1 | 1 | 20 | |
| WSRTU05_VFDRUN2 | Effluent Pump 2 VFD Running | DI | 1 | 1 | 21 | |
| WSRTU05_VFDRUN3 | Effluent Pump 3 VFD Running | DI | 1 | 1 | 22 | |
| WSRTU05_VFDRUN4 | Effluent Pump 4 VFD Running | DI | 1 | 1 | 23 | |
| WSRTU05_VFDRUN5 | Effluent Pump 5 VFD Running | DI | 1 | 1 | 24 | |
| WSRTU05_VFDBYPASS1 | Effluent Pump 1 VFD Bypassed | DI | 1 | 1 | 25 | |
| WSRTU05_VFDBYPASS2 | Effluent Pump 2 VFD Bypassed | DI | 1 | 1 | 26 | |
| WSRTU05_VFDBYPASS3 | Effluent Pump 3 VFD Bypassed | DI | 1 | 1 | 27 | |
| WSRTU05_VFDBYPASS4 | Effluent Pump 4 VFD Bypassed | DI | 1 | 1 | 28 | |
| WSRTU05_VFDBYPASS5 | Effluent Pump 5 VFD Bypassed | DI | 1 | 1 | 29 | |
| WSRTU05_VFDHOOAUTO1 | Effluent Pump 1 HOA in AUTO | DI | 1 | 1 | 30 | |
| WSRTU05_VFDHOOAUTO2 | Effluent Pump 2 HOA in AUTO | DI | 1 | 1 | 31 | |
| WSRTU05_VFDHOOAUTO3 | Effluent Pump 3 HOA in AUTO | DI | 1 | 1 | 32 | |
| WSRTU05_VFDHOOAUTO4 | Effluent Pump 4 HOA in AUTO | DI | 1 | 2 | 1 | |
| WSRTU05_VFDHOOAUTO5 | Effluent Pump 5 HOA in AUTO | DI | 1 | 2 | 2 | |
| WSRTU05_VFDSPDSELWCH1 | Effluent Pump 1 Speed Select Switch | DI | 1 | 2 | 3 | |
| WSRTU05_VFDSPDSELWCH2 | Effluent Pump 2 Speed Select Switch | DI | 1 | 2 | 4 | |
| WSRTU05_VFDSPDSELWCH3 | Effluent Pump 3 Speed Select Switch | DI | 1 | 2 | 5 | |
| WSRTU05_VFDSPDSELWCH4 | Effluent Pump 4 Speed Select Switch | DI | 1 | 2 | 6 | |
| WSRTU05_VFDSPDSELWCH5 | Effluent Pump 5 Speed Select Switch | DI | 1 | 2 | 7 | |
| WSRTU05_PHASEFAILRELAY | Effluent Pump CP Power Fail | DI | 1 | 2 | 8 | |
| WSRTU05_DIESELMONLEAK | Effluent Area Gen Fuel Leak | DI | 1 | 2 | 9 | |
| WSRTU05_DIESELMONPWRFail | Effluent Area Gen Fuel System Power Fail | DI | 1 | 2 | 10 | |
| WSRTU05_DIESELMONWATERLEAK | Effluent Area Gen Water In Fuel | DI | 1 | 2 | 11 | |
| WSRTU05_DIESELMONGENALARM | Effluent Area Gen Fuel Alarm | DI | 1 | 2 | 12 | |
| WSRTU05_Pmp1DiscOn | Effluent Pump 1 Disconnect On | DI | 1 | 2 | 13 | |
| WSRTU05_Pmp2DiscOn | Effluent Pump 2 Disconnect On | DI | 1 | 2 | 14 | |
| WSRTU05_Pmp3DiscOn | Effluent Pump 3 Disconnect On | DI | 1 | 2 | 15 | |
| WSRTU05_Pmp4DiscOn | Effluent Pump 4 Disconnect On | DI | 1 | 2 | 16 | |
| WSRTU05_Pmp5DiscOn | Effluent Pump 5 Disconnect On | DI | 1 | 2 | 17 | |
| WSRTU05_AerationRunning | | DI | 1 | 2 | 18 | Field verify signal. |
| WSRTU05_WaterPumpRunning | | DI | 1 | 2 | 19 | Field verify signal. |
| WSRTU05_LSL506 | Effluent Wet Well Low Level Float | DI | 1 | 2 | 20 | |
| WSRTU05_VFDRUNCMD1_I | Effluent Pump 1 VFD Run Command | DO | 1 | 3 | 1 | |

Existing RTU I/O
(FOR REFERENCE ONLY)

| | | | | | | |
|----------------------|------------------------------------|----|---|---|----|--|
| WSRTU05_VFDRUNCMD2_I | Effluent Pump 2 VFD Run Command | DO | 1 | 3 | 2 | |
| WSRTU05_VFDRUNCMD3_I | Effluent Pump 3 VFD Run Command | DO | 1 | 3 | 3 | |
| WSRTU05_VFDRUNCMD4_I | Effluent Pump 4 VFD Run Command | DO | 1 | 3 | 4 | |
| WSRTU05_VFDRUNCMD5_I | Effluent Pump 5 VFD Run Command | DO | 1 | 3 | 5 | |
| WSRTU05_VFDSPDFB1 | Effluent Pump 1 VFD Speed Feedback | AI | 1 | 4 | 2 | |
| WSRTU05_VFDSPDFB3 | Effluent Pump 3 VFD Speed Feedback | AI | 1 | 4 | 4 | |
| WSRTU05_VFDSPDFB4 | Effluent Pump 4 VFD Speed Feedback | AI | 1 | 4 | 5 | |
| WSRTU05_VFDSPDFB5 | Effluent Pump 5 VFD Speed Feedback | AI | 1 | 4 | 6 | |
| WSRTU05_VFDSPDFB2 | Effluent Pump 2 VFD Speed Feedback | AI | 1 | 4 | 9 | |
| WSRTU05_WETWELLVL | Effluent Wet Well Level | AI | 1 | 4 | 13 | |
| WSRTU05_VFDRUNCMD1 | Effluent Pump 1 VFD Speed Command | AO | 1 | 5 | 1 | |
| WSRTU05_VFDRUNCMD2 | Effluent Pump 2 VFD Speed Command | AO | 1 | 5 | 2 | |
| WSRTU05_VFDRUNCMD3 | Effluent Pump 3 VFD Speed Command | AO | 1 | 5 | 3 | |
| WSRTU05_VFDRUNCMD4 | Effluent Pump 4 VFD Speed Command | AO | 1 | 5 | 4 | |
| WSRTU05_VFDRUNCMD5 | Effluent Pump 5 VFD Speed Command | AO | 1 | 5 | 5 | |

| CONTROL PANEL SCHEDULE | | | | |
|------------------------|--|-------------|------------------------------|---|
| PANEL | PANEL DESCRIPTION | NEMA Rating | APPROXIMATE SIZE (H x W x D) | COMMENTS |
| SCADA NETWORK PANEL | SCADA Network Panel, Sludge Pump and Gas Generation Building 56 (existing SCADA panel) | | | Replace FOPP and field Ethernet switch in existing control panel. |
| MCP-200 | Headworks Screening Control Panel 1 (existing vendor panel) | | | Add FOPP, field Ethernet switch, and DC power supply to existing control panel. |
| MCP-250 | Headworks Screening Control Panel 2 (existing vendor panel) | | | Add FOPP, field Ethernet switch, and DC power supply to existing control panel. |
| MCP-510 | Grit System 1 Control Panel (existing vendor panel) | | | Add FOPP, field Ethernet switch, and DC power supply to existing control panel. |
| MCP-520 | Grit System 2 Control Panel (existing vendor panel) | | | Add FOPP, field Ethernet switch, and DC power supply to existing control panel. |
| 20-SWP-01 | Influent Pump Station Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Detail 2813-026. |
| LCP01-SWP-01 | Headworks Light Pole 01 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Detail 2813-026. |
| 52-SWP-01 | Generator Electrical Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Detail 2813-026. |
| 56-SWP-01 | Sludge Pump and Gas Generator Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Detail 2813-026. |
| CP01-SWP-01 | Camera Pole 01 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 59-SWP-01 | Maintenance Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 60-SWP-01 | Effluent Pump Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| CP02-SWP-01 | Camera Pole 02 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 51-SWP-01 | Chlorine Analyzer Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| CP03-SWP-01 | Camera Pole 03 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |

| CONTROL PANEL SCHEDULE | | | | |
|------------------------|---|-------------|------------------------------|--|
| PANEL | PANEL DESCRIPTION | NEMA Rating | APPROXIMATE SIZE (H x W x D) | COMMENTS |
| CP04-SWP-01 | Camera Pole 04 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 62-SWP-01 | Secondary Electrical Building 2 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 57-SWP-01 | Sludge Transfer Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| CP05-SWP-01 | Camera Pole 05 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| CP06-SWP-01 | Camera Pole 06 Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 10-SWP-01 | Supervisor's Office Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 50-SWP-01 | Chlorine Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 61-SWP-01 | Grease Treatment Facility Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |
| 54-SWP-01 | Operations Building Security Switch Panel | 4X | 24"x24"x8" | White exterior, 3-point latch, padlockable. Provide UPS and 48 VDC power supply for POE Ethernet switch. POE Ethernet switch and Ethernet surge suppression by ESS. See Drawing 05-TY-6002 and Detail 2813-026. |

MEETING AGENDA

Prebid Conference – Annotated (annotations in bold and parenthesis)

PREPARED BY: MAWSS/Jacobs
PROJECT: Wright Smith Jr WWTP Electrical, I & C and HVAC Modifications Project
MEETING DATE: March 16, 2026
MEETING TIME: 9:30:00 a.m.
LOCATION: Wright Smith Jr WWTP

Agenda Items

Attendee Sign-In and Overview of Agenda

Attendance is MANDATORY except for attendees at the Prebid Conference as held on February 9. All potential bidders who did not attend the February 9 Prebid Conference must sign in on the attendance sheet in order to be listed on the bid tabulation and have their bid considered

Introductions

MAWSS

- Doug Cote – Assistant Director - Operations – Not Present
- Jed Barbour – WWTP Chief Operator

Jacobs

- David Carr – Project Manager

Overview of Project

- Purpose of Project – Replace outdated electrical, I & C, HVAC and security components
- Project Funding is through an SRF Loan
 - Bidders must comply with ADEM Supplementary Conditions requirements including DBE/WBE requirements in the preparation and submission of their bids
 - Contractor must adhere to ADEM Supplementary Conditions throughout project
- Project Major Components (See Spec Section 01 11 00 for complete listing)
 - Replace electrical switchgear, multiple MCC's, variable frequency drives and accessories in multiple buildings.
 - Modify SCADA system and fiber optic ring providing fiber interconnectivity to multiple buildings.
 - Install replacement security access control, security lighting, and video security components.
 - Install two new buildings designated as the Operations Electrical Building and the Secondary Electrical Building-2.
 - Replace RTU's in multiple buildings.
 - Replace LED lighting in multiple buildings.
 - Replace and add ventilation fans, air conditioning units and accessories in multiple buildings.
 - Conduct miscellaneous site/civil improvements associated with the new buildings.

- Bid Additive Alternates (per Spec 01 11 00):
 - Alternate 1 – Additional asphalt overlay within the treatment plant site for use at Owner’s direction
 - Alternate 2 – Asphalt replacement within the treatment plant site at Owner’s direction
 - Alternate 3 – Replace a high-mast light lifting mechanism and lights
 - Alternate 4 – Construct a plant sign
 - Alternate 5 – Replace on a unit cost basis selected high mast lights
 - Alternate 6 – Replace on a unit cost basis 120/240V wiring and accessories within selected buildings
 - Alternate 7 – Replace on a unit cost basis 480V wiring and accessories within selected building
 - Alternate 8 – Replace on a unit cost basis 120/240 and 480V wiring and accessories outside existing buildings

Bid Document Distribution

- Electronic Bid documents may be obtained from Charley.golden@jacobs.com as per the invitation to Bid
- Documents Included in Distribution
 - Contract Specifications (Document Volumes 1 through 2)
 - Contract Drawings (Document Volume 3)
 - Model Bid Package (to be printed in color)
 - Geotech Report
 - Selected WWTP As-Builts (in 2 parts)

Supplier Diversity Policy Objectives

- Bidders are encouraged to look for small diverse vendors and/or suppliers that can assist in the project.
- The Minority Business Enterprise (MBEs) and Women’s Business Enterprise (WBEs) utilization objectives from the Supplemental General Conditions Section III are the only DBE Requirements for this project.
- The participation goals as indicated in the SRF Supplemental General Conditions Section III are not met, Contractor must include in their bid evidence of good faith effort per ADEM Supplementary Conditions.

Details of Bid Submittal

- Bids will only be accepted from document holders of record (ie – Obtained from Jacobs) who are represented at either the February 9 or this Prebid Conference as reflected by the sign-in sheet
- MAWSS will receive bid submissions at the Park Forest location as advertised. Bids sent by mail or by Fed Ex must arrive prior to 12:00 pm on day of bid opening. Bids not arriving before the indicated time will not be considered.
- Bid Submission Date and Time – April 6, 2026 @ 12:00 p.m.
- Bids will be opened at the regularly scheduled Board meeting on that date at 1:00 p.m.
- Documents must be printed on the colored paper and accompanied by the tabs on colored paper as per the Information to Bidders and in conformance with the model bid package as issued with the bid documents.
- Include in the Bid Package all items as required by the contract documents.
- The approved manufacturer/supplier table shall be completed as directed in the Proposal.
- Subcontracting Plan must be completed and executed for the bid to be considered as responsive. Subcontracting plan MUST include ALL Subcontractors and Suppliers regardless of their DBE standing
- SSO and Unpermitted Discharge Prevention Notification must be completed and executed for the bid to be considered as responsive.
- Addendums included with the bid may be limited to the addendum form and may exclude attachments to the addendum.
- Bid Bond may be in the form of a Certified Check, Bond, or Irrevocable Letter of Credit acceptable to MAWSS- 5% of Bid not to exceed \$10,000.
- “Other” tab must be followed by the following:
 - Applicable licenses
 - DBE supporting documentation (including indication of Good Faith Efforts for DBE utilization)

- Sealed bids shall be clearly labeled " **Bid for constructing Project # D3755100 - Wright Smith Jr WWTP Electrical, I & C and HVAC Modifications Project, to be opened at 1:00 p.m., Local Time, April 6, 2026**" with bidder's name and Alabama State Contractor's license number and discipline.
- If mailed, place sealed bid package in another envelope
- Basis of Award - Lowest responsive, responsible bidder for lump sum price including any combination of Bid Alternatives, as selected by MAWSS.
- Alternate combinations to be considered will be compliant with Section 01 11 00 Paragraph 1.01.B
- Award Timing- If the amounts of the Proposal are within the budgeted fund, MAWSS may authorize a director's award of the contract subject to the proposal's review and a recommendation of Jacobs.

Construction Details

- Existing Facilities Overview – 28MGD facility must be kept in functional operational service. The scope of work does not interfere with primary flow path but does require temporary measures to maintain power to critical components. Service interruptions may not impact the ability of the plant to receive wastewater or process it to within the permitted discharge standards. (See Spec Section 01 31 13)
- Project Final Completion in 270 calendar days
- Limited Notice to Proceed (LNTP) and General Notice to Proceed (GNTP) per Special Conditions Section 8
 - LNTP will allow Contractor to proceed with critical path component acquisitions and permitting with a delay in the contract time start by up to 180 days as determined per the contract documents.
 - Contractor's Progress Schedule shall reflect his critical path component delivery schedule and must be submitted as per the requirements of the notes of Drawing 01-G-0005
 - Anticipated critical path components are as listed in the Special Conditions and as identified on Drawing 01-G-0005.

Estimated Project Schedule

- Bid Opening – April 6, 2026
- Notice of Award (within 60 days of the bid opening) – late April to mid May
- Contractor to sign contract, furnish bonds and insurance certificates within 10 days of the Notice of Award –May
- Limited Notice to Proceed – Late May to early June
- General Notice to Proceed/Preconstruction Conference – TBD between late May and early December *
- Final Completion (270 days) – TBD between February 2027 and August 2027 *

* Schedule depends upon the time span between the LNTP and the GNTP as derived from the critical path schedule development

General Specification and Drawing Notes

- Note per Section 10.1.27 that MAWSS is exempt from sales tax and Contractor shall adhere to the contract provisions to preclude payment of sales tax.
- Note in the Special Conditions Section 8.04 the added language regarding normal working hours and limitations to and conditions for working outside of normal hours.
- Note in the Special Conditions Section 10 that substitution requests must be received 14 days prior to the opening of bids. There will not be any substitutions for the named manufacturers in the bidder's proposal or as noted in the contract documents.
- A Land Disturbance permit application has been submitted to the City of Mobile and all known comments have been addressed as far as possible lacking additional comment by the City and the identification of the project's Contractor.
- City permitting has required approval of a PUD Modification which has been recommended for approval by City Staff to the Planning Commission. The Planning Commission will consider the application on March 19 followed by the City Council consideration at the next following Council meeting which is expected to be ahead of the Notice of Award.

- Contractor shall complete all permitting applications as required for the prosecution of the project. Where additional engineering information or documents are required, Contractor shall communicate those requirements to Jacobs and Jacobs will provide that information or documents.
- If Alternate 4 is accepted, Contractor will be required to submit a permit application for the sign to the City. Jacobs will provide the partially completed application for completion by the Contractor.
- Construction observation by the Engineer or his delegated representatives is periodic averaging eighteen hours per week over the duration of the contract. Contractor shall coordinate with Engineer for the observation of the work prior to each utility tie in, each concrete pour, and each major work activity commencement and routinely for the duration of the contract to allow Engineer the opportunity to observe the work. Any work indicated by Engineer to be observed by the Engineer shall not be concealed or covered without the Engineer having two week-days' notice of the Contractor's intent to do so.
- Note per Drawings Sheet 01-G-008 and specification Section 01 45 33 Owner will supply specialty inspections and testing on a periodic as-needed basis. Contractor shall coordinate with Engineer or Engineer's designee for each type and instance of testing and special inspections needed throughout the work. Owner may charge Contractor for testing and inspections when conditions as indicated under specification section 01 45 16.13 Par 1.05.F and G occur.
- Special Inspections by Delegated Engineers as per specification section 01 45 16.13 Supplement 3 - Special Inspection Note 2 of 01-G-008 shall be coordinated by the Contractor with the Delegated Engineer. (e.g.: Precast/Prefabricated Buildings)
- Per Specification Section 01 31 13, work by others may be performed concurrently with this project. That work may include the refurbishment of the maintenance building and the replacement of a digester dome. Contractor shall coordinate his work with the work of those contractors to avoid conflicts.
- Per Specification Section 01 50 00, a Contractor's field office must be provided. An Engineer's Field Office is not required.
- Per Specification Section 01 50 00 on-site parking is very limited and Contractor must arrange for off-site parking for its employees
- Per Drawing 01-G-004, erosion control must provide protection of nearby water bodies. Anticipate ADEM inspections of BMP's.
- Per Drawings 01-G-0004 and 01-G-0005, Contractor shall develop a project schedule and sequence of construction to incorporate the delivery timelines as provided by the major component providers to establish the basis for the date of the general notice to proceed and the project schedule for completion of the project within the contract time after the GNTF issuance.

Addenda & Inquiries

- Email or send any questions to Charley.golden@jacobs.com by 4:00p.m. CDT on March 20, 2026.
- Addendum 1 was issued to current plan holders to incorporate changes arising from the February 9 prebid conference and responses to questions raised at this meeting and up through February 10, 2026.
- Addendum 1 included the February 9 prebid conference sign-in sheet and agenda with annotations
- Addendum 2 was issued to include responses to inquiries received through February 26, 2026.
- Addendum 3 will include the March 16 pre-Bid conference sign-in sheet and agenda with annotations along with responses to inquiries received through March 20.

Site Access for Review

The project site is available for review following this meeting as a guided tour. The tour guide is not authorized to respond to any questions and any information offered is not binding. Should additional site information be desired, a site visit prior to March 20, 2026 may be arranged by contacting Jed Barbour (JBARBOUR@mawss.com).

Questions

Questions will be accepted at this meeting. Where the response is readily available it will be made at the meeting. If the response will have a bearing on the contract cost or schedule, that response will be repeated in Addendum 3.



Wright Smith Jr WWTP Electrical, I & C and HVAC Modifications Project Mobile Area Water and Sewer System

Mobile, AL

JACOBS Project No. D3755100

March 16, 2026 at 9:30 AM

2nd Mandatory Pre-Bid Conference Attendee Sign-In

| Organization/Company (Please Print) | Contact Name (Please Print) | Email Address (Please Print) | Signature |
|--|--------------------------------|---------------------------------|-----------|
|--|--------------------------------|---------------------------------|-----------|

Owner

| | | | |
|-------|-------------|--------------------|--|
| MAWSS | Doug Cote | DCote@MAWSS.com | |
| MAWSS | Jed Barbour | JBARBOUR@mawss.com | |

Engineer

| | | | |
|--------|---------------|--------------------------|--|
| Jacobs | David Carr | David.carr10@jacobs.com | |
| Jacobs | Shep Shephard | Shep.Shepherd@jacobs.com | |

Other Attendees

| | | | |
|--------------------------------|----------------|---|--|
| Josh Parker / EMC | Josh Parker | jparker@emcinc.com | |
| Justin Collins / EPB | Justin Collins | Justin.collins@enfrosolutions.com | |
| Scott Goodsell / Guardian | Scott Goodsell | scott.goodsell@guardian-integrators.com | |
| Moody Electric | Ray Webb | Rwebb@moodyelectric.net | |
| SEI Systems | Josh Edwards | josh.edwards@seconz.com | |
| Al Wiggins / Hargrove | Al Wiggins | awiggins@hargrove-epc.com | |
| Hargrove | Bryan Sargent | bsargent@hargrove-epc.com | |
| Blake Bunch / Yes Construction | Blake Bunch | blake_bunch@yesconstruction.com | |
| Kim Dennis | Kim Dennis | FDennis@moodyelectric.net | |
| moody's Electric | Kim Dennis | FDennis@moodyelectric.net | |
| EP Breux | Guy Whaley | guy.whaley@enfrosolutions.com | |
| Pye Barker FS | David Aguirre | David.Aguirre@pyebarkerfs.com | |
| | | | |
| | | | |
| | | | |